



AVO INTERNATIONAL

INSTRUCTION MANUAL

For

UNIVERSAL PROTECTIVE RELAY TEST SET

MODEL SR-90

It is essential that this instruction book be read thoroughly before putting the equipment in service.

REVISION HISTORY

<u>Revision</u>	<u>ECN #</u>	<u>Date</u>
4	25689	01/13/94

IMPORTANT

The information and data contained within this instruction manual are proprietary with AVO MULTI-AMP Corporation. The equipment described herein may be protected by one or more U.S. letters patent. AVO MULTI-AMP specifically reserves to itself all rights to such proprietary information as well as all rights under any such patent, none of which is waived by the submission of this instruction manual to anyone.

The recipient, if a Government agency, acknowledges that this instruction book and the equipment described were procured with "Limited Rights" to technical data as described in ASPR 9-203 (b).

TABLE OF CONTENTS

SECTION	PAGE
A. GENERAL DESCRIPTION AND SPECIFICATIONS	Bulletin
THEORY OF OPERATION	1
DESCRIPTION	2
UNIT #1 - CONTROL SECTION	2
UNIT #2 - AUXILIARY SECTION	9
SELECTION OF OUTPUT TAPS	15
SERVICE DATA	16
WARRANTY	17
OVERLOAD CAPABILITY OF UNIT #1	18
TESTING INDUCTION DISC OVERCURRENT RELAYS	21
Westinghouse Type CO	21
General Electric Type IAC	21
TESTING OVER/UNDER VOLTAGE RELAYS	25
Westinghouse Type CV	25
General Electric Type IAV	25
TESTING PERCENTAGE DIFFERENTIAL RELAYS	28
Westinghouse Type CA	28
General Electric Type IJD	28
TRANSFORMER DIFFERENTIAL RELAY WITH	32
PERCENTAGE AND HARMONIC RESTRAINT	32
General Electric Type BDD	32
TYPICAL TEST FOR DC AUXILIARY RELAYS	37
TESTING INSULATION RESISTANCE	39
TESTING I.T.E. CIRCUIT SHIELD	41
SOLID-STATE OVERCURRENT RELAYS	41
DIRECTIONAL OVERCURRENT RELAY	45
Westinghouse Type CR	45
General Electric Type IBC	45
VOLTAGE RESTRAINT OVERCURRENT RELAY	48
General Electric Type IJCV	48
VOLTAGE CONTROLLED OVERCURRENT RELAY	51
Westinghouse Type COV	51

TRANSFORMER DIFFERENTIAL RELAY WITH	54
PERCENTAGE AND HARMONIC RESTRAINT	54
Westinghouse Type HU	54
CURRENT PHASE BALANCE RELAYS	58
Westinghouse Type CM	58
General Electric Type IJC	58
HIGH IMPEDANCE BUS DIFFERENTIAL RELAY	65
Westinghouse Type KAB	65
DIFFERENTIAL VOLTAGE RELAY	68
General Electric Type PVD	68
TESTING INSTANTANEOUS VOLTAGE RELAYS	71
Westinghouse Type SV, SV-1	71
General Electric Type PJV	71
PILOT WIRE RELAY	73
Westinghouse Type HCB	73
TESTING GROUND DIRECTIONAL OVERCURRENT RELAYS	75
Westinghouse Type IRD, KRD and	75
General Electric Type JBCG	75
FAULT DETECTOR RELAY	79
General Electric Type CHC	79
SCHEMATIC AND PARTS LIST	81


TABLE OF CONTENTS Continued

---This table lists alphabetically by type, relays covered by procedures in this manual.

<u>Relay</u>		<u>Page</u>
BDD	G.E. - Harmonic Restraint Transformer Differential	32
CA	Westinghouse Percentage Differential	28
CHC	G.E. Fault Detector	80
CM	Westinghouse Current Phase Balance	62
CO	Westinghouse Voltage Controlled Overcurrent	21
COV	Westinghouse Voltage Controlled Overcurrent	52
CR	Westinghouse Directional Overcurrent	46
CV	Westinghouse Induction Disc Over/Under Voltage	25
HCB	Westinghouse Pilot Wire	74
HU	Westinghouse Harmonic Restraint Differential	55
IAC	G.E. Induction Disc Overcurrent	21
IAV	G.E. Induction Disc Over/Under Voltage	25

TABLE OF CONTENTS Continued

<u>Relay</u>	<u>Section</u>	<u>Page</u>
IBC	G.E. Directional Overcurrent	46
IJC	G.E. Current Phase Balance	59
IJCV	G.E. Voltage Restraint Overcurrent	49
IJD	G.E. Percentage Differential	28
IRD	Westinghouse Ground Directional Overcurrent	76
I.T.E.	Solid State Overcurrent	42
JBCG	G.E. Ground Directional Overcurrent	76
KAB	Westinghouse High Impedance Bus Differential	66
PJV	G.E. Instantaneous Voltage	72
PVD	G.E. High Impedance Bus Differential	69
SV, SV-1	Westinghouse Instantaneous Voltage	72



Universal Protective Relay Test Set

MULTI-AMP® Model SR-90

- Digital metering
- Memory ammeter
- Units 1 and 2 work independently

DESCRIPTION

The Multi-Amp® Model SR-90 Universal Protective Relay Test Set is a multipurpose, two-piece test set that accurately and efficiently tests electromechanical and solid-state protective relays.

Model SR-90 continues our commitment of providing you with a versatile, protective relay test set that is field portable and has sufficient power (1.4 kVA) for testing any protective device requiring up to 420 amperes.

Model SR-90 is designed so the main control section (Unit 1) and the auxiliary section (Unit 2) can be used independently from each other for testing "simple" protective devices.

To perform testing of more "complex" relays, Units 1 and 2 are easily interconnected to provide four simultaneous outputs of ac current or ac voltage, and dc current or dc voltage.

APPLICATIONS

Model SR-90 is designed for calibrating, acceptance testing and troubleshooting of protective relays, small molded-case circuit breakers and motor overload relays, and for timing circuit breakers. This test set is ideal for field, shop or laboratory use at utilities, manufacturing plants, commercial complexes or other facilities that perform preventative maintenance on electrical equipment.

Types of Relays You Can Test with Model SR-90

Table I - Unit 1	
Relay Types	IEEE Device Number
Voltage-Controlled Overcurrent	27/51
Instantaneous Overcurrent	50
Overcurrent	51
Reclosing	79
Tripping	94
Molded-Case Circuit Breakers*	52
Motor Overload*	51/86
*The 140-ampere output tap may be overloaded up to three times its rating for short-time overloads.	

Table II - Units 1 and 2	
Relay Types (all of the protective relays in Table I plus:)	IEEE Device Number
Time Delay	2
DC Under/Overcurrent	37/76
Under/Overtension	27/59
Directional Overcurrent	67
Ground Directional Overcurrent	67N
Differential	87

Table III - Units 1 and 2 (with Model PSA-100 Combined Phase Shifter/Phase Angle Meter/Multimeter)	
Relay Types	IEEE Device Number
Distance	21
Synchronizing	25
Directional Power	32
Negative Sequence Overcurrent	46

FEATURES AND BENEFITS

The Control Unit—Unit 1

Includes the main current transformer with five selectable current ranges of:

- 0 to 8.75 amperes at 0 to 160 volts
- 0 to 17.5 amperes at 0 to 80 volts
- 0 to 35 amperes at 0 to 40 volts
- 0 to 70 amperes at 0 to 20 volts
- 0 to 140 amperes at 0 to 10 volts

- Also features four selectable ammeter ranges of 2 amperes, 20 amperes, 200 amperes and 2 kA

- Memory ammeter: preset test currents when testing small, molded-case circuit breakers and motor overload relays. Reduces preheating the relay under test, thus avoiding the possibility of producing erroneous test current readings. Pinpoints instantaneous pickup points on overcurrent and current differential relays.

- Incorporates a metered voltage range of 0 to 160 volts using the 8.75-ampere tap with the ac voltmeter selectable to either 20 or 200 volts

- Selectable dc current or voltage is provided with output ranges of 2 amperes dc or 5 amperes dc and 150 Vdc or 300 Vdc.

- Solid-state, multifunction, digital timer

The Auxiliary Unit—Unit 2

Includes outputs for:

- Additional ac current source with a range of 0 to 25 amperes and ac voltage source with selectable ranges of 0 to 300 volts or 0 to 600 volts

- Harmonic restraint test source for providing half-wave rectified dc current from the 0- to 25-ampere output

- AC initiate switch for energizing the test set in normal mode (connected to Unit 1), or in the bypass mode when it is operating as a stand-alone unit

Also includes:


- An ac/dc voltage source, with selectable ranges of either 0 to 150 volts or 0 to 300 volts

- A voltage relay section for dynamic testing voltage relays


- A directional element test section for testing single-phase, directional elements. Five calibrated values are provided.

- The capacity to measure external ac or dc voltage when connected to Unit 2.


- A 500-Vdc insulation resistance test section



The Control Unit (Unit 1) of Model SR-90



The Auxiliary Unit (Unit 2) of Model SR-90



Model SR-90, with Units 1 and 2 stacked, tests a current differential relay in a panel.

Other Features and Benefits of Model SR-90

- High-accuracy, all-digital metering: avoids interpolation of readings associated with analog meters. This allows the user to be more productive by taking faster more accurate readings of voltage and current.
 - Digital timer: Multifunction, switch-selectable timer increases accuracy and flexibility with independent start and stop gates. Eliminates the need for a separate timer for timing circuit breakers. Also, reclosing relays can be timed cumulatively.
 - Easy-to-read, backlit LED displays: all-digital with $3\frac{1}{2}$ -digit, 0.5-in. (12-mm) displays. Current or voltage values can be read in all light levels, including direct sunlight and low-light conditions.
 - Initiate control circuit: provides both "momentary" and "maintain" modes to control output duration. The momentary mode, in conjunction with the memory ammeter, permits "pulsed" application of the output to avoid damage or overheating of the relay while setting the test current.
- In the maintain mode, the output remains energized until manually

turned off, or when performing timing tests, until the relay under test operates, which stops the timer and de-energizes the output. Includes an external jack to initiate output away from the test set.

- Higher ac voltage output: Unit 2 features a 0- to 600-volt output terminal for testing relays rated up to 600 volts.
- Two high-capacity ac current outputs: designed to operate entirely independently of each other. One current channel provides five adjustable ranges, each rated at 1.4 kVA. The second channel is continuously adjustable from 0 to 25 amperes at 1 kVA — more than sufficient capacity to perform slope tests on high-impedance differential relays.
- EMI- and RF-shielding: reduces interference and prevents misoperation when using the test set in EHV switchyards and near portable, two-way radios
- Rack mountable: fixtures are provided so chassis can be installed in a standard, 19-in. (483-mm) rack.
- Environmentally tested: To simulate the worst field conditions possible, Model SR-90 has been tested and qualified in accordance with MIL-STD-810 for temperature, shock and vibration

resistance. The units are forced-air cooled to extend operation of the test set in high ambient temperatures [will provide rated output at 122° F (50° C) for 5 minutes with an equal cool-down time].

- Rugged, weatherproof enclosure: Model SR-90 is available in a rugged, portable enclosure, or it may be ordered without the enclosure for easy mounting in a standard, 19-in. (483-mm) rack.

The ribbed enclosure is made of durable, medium-density, polyethylene plastic—flexible enough to absorb shocks and vibration, yet lightweight. The specially designed ribs add strength and protect the latches and handles during rough handling. The units are easily stacked with the ribs acting to interlock both units together.

The enclosure is completely weather-proof and noncorrosive. The gasketed tongue and grooved aluminum valance of the front and back lids and the lock-down, military-style latches protect the test set from dust and water intrusion. The front and back lids can be removed quickly when putting the unit into service, yet remain sealed and secure during transport or storage.

- Internal structure: Panel-mounted printed circuit boards with locking ribbon connections improve reliability and make Model SR-90 easy to service.

SPECIFICATIONS

Input

115 V $\pm 10\%$, 50/60 Hz, 1 ϕ
OR
230 V $\pm 10\%$, 50/60 Hz, 1 ϕ

Outputs

Unit 1

0 to 140 A ac at 10 V
0 to 70 A ac at 20 V
0 to 35 A ac at 40 V
0 to 17.5 A ac at 80 V
0 to 8.75 A ac at 160 V
0 to 5 A dc at 8 V
0 to 150 Vdc at 1.0 A
0 to 300 Vdc at 0.5 A

Unit 2

0 to 25 A ac at 40 V
0 to 300 Vac at 0.5 A
0 to 600 Vac at 0.25 A
0 to 150 Vac at 1.0 A
0 to 300 Vac at 0.5 A
0 to 150 Vdc at 1.0 A
0 to 300 Vdc at 0.5 A
0 to 500 Vdc

Instrumentation

Model SR-90 features all-digital instrumentation with $3\frac{1}{2}$ -digit, 0.5-in. (12-mm) backlit LED displays. All accuracies are stated for 10 to 100% of range.

Unit 1—Control Unit**AC Ammeter/Voltmeter**

Ranges (switch-selected)

0 to 1.999/19.99/199.9/1999 A
0 to 19.99/199.9 V

Accuracy: $\pm 1\%$ of reading, ± 1 digit

DC Ammeter/Voltmeter

Ranges (switch-selected)

0 to 1.999/5 A
0 to 199.9/300 V

Accuracy: $\pm 1\%$ of reading, ± 1 digit

Unit 2—Auxiliary Unit**AC Ammeter/Voltmeter**

Ranges (switch-selected)

0 to 1.999/25 A
0 to 19.99/199.9/600 V

Accuracy: $\pm 1\%$ of reading, ± 1 digit

Multifunction AC/DC Voltmeter/Insulation Tester

Voltmeter also may be used as an independent instrument in conjunction with the voltmeter selector switch to measure external ac or dc voltages up to 300 V.

Ranges (switch-selected)

Voltage: 0 to 1.999/19.99/
199.9/500 V

Accuracy: $\pm 1\%$ of reading,
 ± 1 digit

Resistance: 0.1 to 19.99 M Ω

Timer—Unit 1

The solid-state, digital timer measures the elapsed time of the test in either seconds or cycles. Extensive shielding and noise-suppression circuitry is incorporated to ensure accurate and reliable operation under the most demanding field conditions. Also utilizes a crystal-controlled oscillator, allowing timer accuracy to be unaffected by the power line frequency

Display: 6-digit, 0.3-in. (7-mm) LED display

Ranges (switch-selected)

0 to 99.9999 s
0 to 9999.99 s
0 to 99999.9 cycles

Accuracy: $\pm 0.005\%$ of range, ± 1 digit in the seconds mode; ± 0.5 in cycles mode

Start/Stop Gates

Two independent pushbuttons provide these timer operating modes:

- Timer starts/stops when dry contact is opened/closed.

- Timer starts/stops when voltage is applied/removed; ac potential (60 to 300 V rms) or dc potential (5 to 300 V).
- Timer starts when output is initiated.
- Timer stops when output current is interrupted.

Latch On/Off

A four-function pushbutton is used with the start/stop pushbuttons and start/stop binding posts to increase control over starting and stopping the timer.

Operating Temperature

32 to 122° F (0 to 50° C)

Storage Temperature

-4 to +158° F (-20 to +70° C)

Dimensions**With Lids On**

10.75 H x 21 W x 24.5 D in.
273 H x 533 W x 622 D mm

With Lids Off

10.75 H x 21 W x 18.5 D in.
273 H x 533 W x 470 D mm

Weight**With Lids On**

Unit 1: 80 lb (36 kg)
Unit 2: 72 lb (33 kg)

With Lids Off

Unit 1: 74 lb (34 kg)
Unit 2: 66 lb (30 kg)

ORDERING INFORMATION

Item (Qty)	Cat. No.	Item (Qty)	Cat. No.
Model SR-90 with 115-volt input,		Cables	
50/60 Hz in standard enclosure		Interconnect cable (1)	12681
Units 1 and 2	SR-90-115	Input power cable, Unit 1 (1)	12683
Unit 1 only	SR-90-115-1	Input power cable, Unit 2 (1)	12684
Unit 2 only	SR-90-115-2	Interconnect power cable (1)	12685
Model SR-90 with 115-volt input,		Remote initiate cable (1)	12806
50/60 Hz without enclosure, for rack mounting		Fuses	
Units 1 and 2	SR-90-115/RK	0.5 A, 250 V (5)	982
Unit 1 only	SR-90-115-1/RK	1.0 A, 250 V (5)	4139
Unit 2 only	SR-90-115-2/RK	1.5 A, 250 V (5)	950
Model SR-90 with 230-volt input,		3 A, 250 V (5)	951
50/60 Hz in standard enclosure		5 A, 250 V (5)	952
Units 1 and 2	SR-90-230	8 A, 250 V (5)	962
Unit 1 only	SR-90-230-1	15 A, 250 V (5)	963
Unit 2 only	SR-90-230-2	20 A, 250 V (5)	9043
Model SR-90 with 230-volt input,		Ground lead (1)	11258
50/60 Hz without enclosure, for rack mounting		Unit 1 test leads	
Units 1 and 2	SR-90-230/RK	Current (1 pr)	7934
Unit 1 only	SR-90-230-1/RK	Voltage (2 pr)	1282
Unit 2 only	SR-90-230-2/RK	PAM Input (1 pr)	12680
Included Accessories		Unit 2 test leads	
Carrying case for the following standard		Current (1 pr)	7934
accessories below (1 per unit)	11437	Voltage (2 pr)	1282
		High-voltage leads (1 pr)	1125
		Instruction manual (1)	12675

THEORY OF OPERATION

Multi-Amp Model SR-90 is housed in a metal chassis shielded from EMI or RF interference. The ribbed enclosure is made of durable, medium-density polyethylene plastic, lightweight, yet flexible enough to absorb tremendous shock and vibration, each unit is equipped with carrying handles and removable hinged covers which protect instruments and controls during transportation and storage. A single multiple conductor cable with screw-in plugs on each end is provided to interconnect the two sections. Facilities are incorporated so that up to four independent outputs can be obtained simultaneously, with both units of the SR-90 interconnected and initiated simultaneously.

The control unit, Unit #1, incorporates the main current output transformer with selectable current ranges of 8.75A @ 0-160V; 17.5A @ 0-80V; 35A @ 0-40V; 70A @ 0-20V; and 140A @ 0-10V. The Ammeter range selection is either 2A; 20A; 200A; or 1KA. There is also a metered voltage range of 0-160V using the 8.75A @ 0-160V tap, with an AC Voltmeter selector switch selectable for either 20V or 200V. An additional section of selectable DC current or voltage is provided with output ranges of 2ADC, 5ADC or 150VDC, 300VDC, which is useful for testing target and seal-in units, operation indicators, DC voltage relays and providing DC logic voltage for solid-state protective relays. The control section also contains the primary initiate control circuitry of the test set along with the solid state digital timer, offering the user a multiple variety of timer options.

The auxiliary unit, Unit #2, contains outputs for an additional AC current source with a range of 0-25A, an AC voltage source with selectable sources of 0-300V or 0-600V, a Harmonic Restraint test switch, and an AC Initiate switch for selecting Normal operation of the test set when interconnected to Unit #1, (Normal Mode), or as a stand-alone unit, in the Bypass mode of operation. Unit #2 also incorporates an Auxiliary section with capabilities for an additional AC/DC voltage source, with selectable ranges of either 0-150V or 0-300V, a Voltage Relay section for dynamic testing of Voltage Relays, and a Directional Element Test section with five selectable values, an Insulation Resistance Test circuit, and the capacity to measure an external AC or DC voltage.

Model SR-90 is designed so that the main control section Unit #1 can be used independently from Unit #2, for the convenience in testing overcurrent relays and similar devices. To obtain the additional voltage or current sources for more 'complex' relays, both Unit #1 and Unit #2 must be interconnected.

DESCRIPTION OF CONTROLS AND INSTRUMENTATION

UNIT #1 - CONTROL SECTION

The Control Section, (Unit #1), of Model SR-90 comprises of two output channels; one is controlled by the large AC CONTROL knob and the other is controlled by the smaller DC or VERNIER knob. The following is a description of the controls and instrumentation on Unit #1.

FRONT PANEL

POWER ON/OFF Switch: Functions as main input switch for the test set.

INITIATE CONTROL Circuit: The Initiate Control Circuit of Model SR-90 provides the ability for Initiating the test set, establishing the mode of initiation either by energizing the circuit **MOMENTARY** or **MAINTAINED** and a **RESET** switch for resetting the digital timer.

INITIATE Button: The **INITIATE** button serves to start operation of the test set. A small **LED** above the button indicates whenever the test set is initiated.

MOM/MAINT Button: **MOM.** (Momentary):

The selected outputs will remain energized as long as the **INITIATE** switch is held depressed, until the contacts of the device under test close or the operator releases the **INITIATE** switch.

MAINT. (Maintain):

The function of this position is exactly the same as above except that the **INITIATE** button only needs to be depressed momentarily to lock-in a circuit which maintains the output of the test set. The test set will remain energized until the contacts under test change state or the operator depresses the **RESET** switch.

RESET Pushbutton:

It is always necessary to reset the Model SR-90 upon initial power up of the test set. This action will reset the digital timer to all zero. Therefore, should the test set fail to INITIATE upon depressing the INITIATE button, RESET the TIMER and then re-initiate the test set. Whenever the test set is in the MOM. mode it will be necessary to RESET the TIMER, due to an external operation of a contact closure from the protective device under test.

TIMER:

Used to measure the elapsed time of operation of the device under test. The Timer is equipped with a CYCLES/SECONDS Switch for selection of either a 0.01 seconds, 0.0001 seconds, or a cycles counting mode. Additionally, the RESET button is provided in the INITIATE CONTROL section, to reset the timer initiate circuitry and display.

TIMER CONTROL Section:

Selectable modes of operation convenient for the operator depending upon the type of test to be performed.

INITIATE

This function switch is the automatic default method of testing. Upon initiation of the Model SR-90 the TIMER will commence timing.

V.RLY/DO

This function switch should be used when performing timing tests on Under/Over Voltage Relays and timing the Drop Out of circuit breaker contacts or protective relay contacts.

CURRENT

This function switch is for testing current devices without allowing them to become damaged due to heating or performing time run performance tests. The current initiation point is set to trigger at approximately 8 degrees of the current sine wave, which equates to about 0.3703 milli seconds of current will be sensed by the current device under test, before the TIMER will actually start timing. The TIMER stops when the output current is interrupted by the device under test.

EXTERNAL

This function switch is selected for testing or monitoring external contacts, such as the 52a and 52b contacts of Low to EHV Circuit Breakers, the timing of protective relay protection schemes, conveyor control speed adjustments for coal feeders or material handling systems.

START/STOP Selector Pushbuttons:

Two identical independent four-position pushbutton switches are provided for selection of the Start and Stop/Monitor gates. The left pushbutton switch is used to select the Start gate operating mode, while the right pushbutton is used to select the Stop mode. In addition, the Stop Selector Switch is also used in conjunction with the Monitor Selector Switch for selecting the desired Monitor mode of operation. The following modes are provided for both the START gate and the STOP/MONITOR gate:

N.O. DRY CONTACTS:

The function of this position is to monitor contacts which have Normally Open Dry contacts of the device under test. The TIMER starts or stops at the closure of a normally open contact or conduction through a semiconductor device such as an SCR, triac or transistor.

N.C. DRY CONTACTS:

The function of this position is to monitor contacts which have Normally Closed Dry Contacts of the device under test. The TIMER starts or stops at the opening of a normally closed contact or when conduction through a semiconductor device such as an SCR, triac or transistor is interrupted.

VOLTAGE APPLIED:

The function of this position is to monitor contacts which have an AC/DC voltage across the contacts of the device under test. The TIMER starts or stops when an AC potential (60-300V RMS) or DC potential (5-300V) is applied.

VOLTAGE REMOVED:

The function of this position is to monitor contacts which have an AC/DC voltage removed from the

contacts of the device under test. The timer starts or stops when AC potential (60-300V RMS) or DC potential (5-300V) is removed.

**LATCHED ON/OFF
Pushbutton:**

This four function pushbutton is used in conjunction with the START/STOP pushbuttons and the START/STOP binding posts in order to supervise the starting and stopping of the timer.

STOP LATCH:

When the stop circuit is latched ON the stop latch allows timing to be stopped at the first operation of any stop gate. When the STOP circuit is latched OFF, the stop latch allows timing to be stopped by any stop gate and then restarted if the stop gate reverses (provided a start gate is still energized) and stopped when the stop gate is again energized.

START LATCH:

When the start circuit is latched ON, the start latch allows timing to be initiated by any start gate and to be stopped only by the STOP gate selected. When the START circuit is latched OFF, the start latch allows timing to be initiated by any start gate and stopped when the start gate is reversed.

**STOP/MONITOR Binding
Posts:**

These binding posts perform a dual function for monitoring a protective relay's trip circuit or as the STOP Gate of the digital timer. The trip circuit contacts of either an electromechanical relay or a solid state relay with or without a SCR voltage applied are connected.

**MONITOR/HORN
Pushbutton:**

A CONTINUITY light or TONE generator can be used to monitor contact action or circuit continuity, when MONITOR/HORN LED's are illuminated the continuity light and the tone generator are turned ON. When the trip circuit connected to the STOP/MONITOR binding posts is closed, an audible tone is generated and the CONTINUITY light is illuminated. NOTE: when the MONITOR circuit is activated the HORN circuit is OFF, but when the HORN circuit is activated both the MONITOR circuit and the HORN circuit are ON.

AC Ammeter/Voltmeter:	Ammeter measures the AC output current. The meter is equipped with a CONTINUOUS or MEMORY switch. The CONTINUOUS position allows the meter to continuously display the current or voltage setting of the AC CONTROL Knob, the MEMORY position is utilized to set an instantaneous current level, using the MOM, INITIATE control switch, for testing instantaneous relays, pre-setting current levels for time testing of overcurrent devices, and testing current differential relays. The Voltmeter is connected to the 8.75A @ 160V output tap to meter the voltage output.
AC Ammeter/Voltmeter Range Switch:	Selects full scale range of the AC Ammeter/Voltmeter. For highest resolution, always use the lowest range which will not over-range the meter.
DC Ammeter/Voltmeter:	Measures the DC output current or voltage.
DC Ammeter/Voltmeter Range Switch:	Selects full scale range of the DC ammeter or voltmeter.
DC or VERNIER Control Knob and DC/VERNIER Switch:	When the DC/VERNIER Switch is in the DC position, this knob controls the DC CURRENT or VOLTAGE output. When in the VERNIER position, it is a fine-adjustment for the main AC CURRENT or VOLTAGE output.

DC Output Binding Posts
(Red +, Black -):

Binding posts for the DC CURRENT or VOLTAGE output.

AC CONTROL Knob:

This knob controls the main AC current output of Unit #1. The AC CONTROL Knob also performs a dual function to provide either AC Current or Voltage.

AC Output Terminals:

The output controlled by the main AC control knob is available at the terminals located at the bottom of Unit #1. There are two common terminals and five output ranges. Each range can be used either as source of AC voltage or AC current, but only the 8.75A @ 0-160V tap is metered on the AC Voltmeter located directly above the AC Control knob. All other taps can be utilized as an AC Voltage source, but the operator must use an external voltmeter for monitoring the voltage applied.

Each range is capable of supplying the indicated current, provided the voltage is sufficient to push the current through the impedance of the load circuit. Where the voltage is sufficient to "push" higher than rated current through the impedance of the load circuit, the current ratings are designed to be overloaded for short durations. For overload capabilities, refer to the OVERLOAD CAPABILITY OF UNIT #1 section of this manual.

P.A.M. Output:

This output provides a 10 to 30 volt output to a voltage coil of a phase angle meter. Note: This is a voltage output and *not* a current input which was the design concept for previous SR units. It should also be noted that this voltage is in-phase with the AC current output of Unit #1.

WARNING:

DO NOT apply this output to a phase angle meter current coil.

UNIT #1 - BACK PANEL

Input Line Cord:

The test set is equipped with a standard 3-prong line cord which is part of the accessory kit, it connects to the male plug on the back panel of Unit #1. The nameplate should be checked for verification of input voltage before connecting the line cord to the source of power.

UNIT #2 AC POWER:	This receptacle is used when Unit #1 is to be connected with Unit #2 and input voltage from Unit #1 is supplied to Unit #2.
UNIT #2 INTERCONNECT:	This receptacle is used when Unit #1 is to be connected with Unit #2 and the INITIATE CONTROL, the TIMER, or the TIMER CONTROL circuitry of Unit #1 is to be utilized to compliment Unit #2.
FREQUENCY Select Switch:	This switch is equipped on Unit #1 to select the frequency time base for the TIMER, at either 50 or 60 Hz, and the input voltage frequency.
EXT. INITIATE Jack:	The test set can be initiated from a remote location by closing a circuit plugged into the EXT. INITIATE jack.
120V SYNC. Binding Posts:	These terminals are energized with 120 volts whenever the unit is initiated. This voltage may be used as a control source to initiate an external device such as an auxiliary relay.
Fuses - 115V, [230V]	
F1 - 15A, [10A]	Protects the AC CONTROL Output Transformer and the wiper arm of the AC CONTROL variable transformer.
F2 - 3A, [1.5A]	Protects the AC/DC VERNIER Output Transformer and the wiper arm of the AC/DC VERNIER variable transformer.
F3 & F6 - 5A, [2A]	Provides overload and short-circuit protection for the main AC output circuit.
F4 - 1A, [0.5A]	Protects the line input filter from abnormal current surges.
F5 - 0.5A, [0.5A]	Provides overload and short-circuit protection for the main control logic printed circuit board.
F7 & F8 - 20A, [10A]	Provides overload and short-circuit protection for the entire test set and its connection to the users AC voltage distribution outlet.
F9 - 5A, [5A]	Protects the full wave bridge rectifier circuitry necessary for generating the DC voltage output.

UNIT #2 - AUXILIARY SECTION

The Auxiliary Section, (Unit #2), of Model SR-90 comprises of two output channels on the test set; one controlled by a large AC ADJUST Control knob and the other by a small AUX ADJUST Control knob. The following section provides a description of the various controls and instrumentation in the Auxiliary Section, (Unit #2), of Model SR-90.

AC Ammeter/Voltmeter:	Measures the magnitude of the 0-25A, 0-300V, or 0-600V output available at the Blue and White output binding posts.
AC Ammeter/Voltmeter Range Switch:	Selects full scale range of the AC Ammeter/Voltmeter. For highest resolution, always use the lowest range which will not over-range the meter.
AC INITIATE BYPASS/NORMAL Switch:	This switch is used to establish the Initiate Control circuitry for the 0-25A/0-600V output. When the switch is in the NORMAL position the 0-25A/0-600V output is energized by the INITIATE CONTROL circuitry of Unit #1. When the switch is in the CENTER position the 0-25A/0-600V output is OFF, if switched to the BYPASS position the 0-25A/0-600V output is ON.

WARNING

IF THE RED LED ABOVE THE 0-25A/0-600V BINDING POSTS IS ILLUMINATED, THE CHANNEL IS ON. IF THE RED LED IS FLASHING, THE CURRENT CIRCUIT UNDER TEST IS OPEN OR THE VOLTAGE CIRCUIT UNDER TEST IS SHUNT. IF UNIT #2 IS NOT INTERCONNECTED TO UNIT #1, IN ORDER TO REESTABLISH THE OUTPUT, MOVE THE AC INITIATE SWITCH TO THE CENTER POSITION AND BACK TO THE BYPASS POSITION.

OUTPUT SELECT Switch 0-25A/0-300V/0-600V:	This switch is used to select either a current output of 0 to 25 amperes at 40 volts, a voltage output of 0 to 300 volts at 1.0 amperes, or a voltage output of 0 to 600 volts at 0.5 amperes; the current or voltage output is available at the Blue and White output binding posts labeled 0-25A or 0-600V AC. The White binding post is the instantaneous ($\pm$) polarity binding post.
---	---

CAUTION:

THIS IS AN INTERLOCKING SWITCH. PULL THE SELECTION SWITCH OUTWARDS, THEN MOVE TO THE DESIRED POSITION AND RELEASE.

AC ADJUST Control Knob:

This knob allows the user to adjust the AC Current or Voltage output of Unit #2.

HARMONIC RESTRAINT/NORMAL Switch:

In the NORMAL position, the HARMONIC RESTRAINT circuitry is completely isolated. When switched to the HARMONIC RESTRAINT position, the 0 to 25A Output terminals of Unit #2 will provide a half-wave rectified DC current output for testing the harmonic restraint element in harmonic restraint differential relays. The output magnitude is controlled by the large AC ADJUST Control knob of Unit #2, while the amplitude of the half-wave rectified DC current is displayed on the DC Ammeter of Unit #1. NOTE: The DC Ammeter Selector Switch on Unit #1 must be set at 5A.

AUXILIARY OUTPUT SECTION

VOLTAGE SECTION:

- 0-150V DC:** 0-150V DC @ 1.0 amperes is available at the AC/DC OUTPUT binding posts.
- 0-300V DC:** 0-300V DC @ 0.5 amperes is available at the AC/DC OUTPUT binding posts.
- 0-150V AC:** 0-150V AC @ 1.0 amperes is available at the AC/DC OUTPUT binding posts. The Black binding post is the ($\pm$) instantaneous polarity binding post.
- 0-300V AC:** 0-300V AC @ 0.5 amperes is available at the AC/DC OUTPUT binding posts. The Black binding post is the ($\pm$) instantaneous polarity binding post.
- IR TEST:** 0-500 volts DC for measuring insulation resistance. The output is available at the small Red and Black pin sockets labeled IR TEST and is controlled by the AUX ADJUST knob.

V. RELAY SECTION:

Used in conjunction with the voltage relay and directional element test circuits. The functions of each position are detailed as follows:

NORMAL: Used to apply the normal relay voltage to the voltage relay under test. The output is available at the AC/DC OUTPUT binding posts, displayed on the AC Voltmeter, and is controlled by the AC ADJUST control knob.

FAULT: Used to preset the fault voltage to be applied to voltage relay under test. When in this position, the normal voltage set in the NORMAL position remains on the relay. The magnitude of the fault voltage is controlled by the AUX ADJUST control knob and is displayed on the AUX Voltmeter.

TEST: The fault voltage, which was preset in the V. RLY. FAULT position, is applied to the relay and the digital timer is simultaneously started, provided the TIMER CONTROL selection has been preset to the V.RLY/DO position. When the relay operates, the timer will stop.

D.E.T. Section: Five ranges are provided to conduct pickup tests on directional elements. To obtain a voltage and a current exactly in phase, the instantaneous polarity terminal of the relay's current coil is connected to the Blue 0-25A or 0-600V AC binding post. The non-polarity terminal is connected to the Black AUXILIARY OUTPUTS binding post. The instantaneous polarity terminal of the relay's potential coil is connected to the Black AUXILIARY OUTPUTS binding post and the non-polarity terminal is connected to the Red AUXILIARY OUTPUTS binding post.

The magnitude of the voltage and current is controlled by the AC ADJUST Control knob, the current magnitude is displayed in the AC Ammeter and the voltage amplitude is displayed in the AUX Voltmeter.

Reversing either the current coil or the potential coil connections will result in the current and potential being 180° out of phase.

AUX VOLTMETER SECTION

AUX AC/DC Voltmeter: Used in conjunction with the VOLTMETER CIRCUIT SELECTOR Switch and the VOLTMETER RANGE Switch, the magnitude of the various potential outputs of the test set, or of an external AC or DC potential may be measured.

AUX Voltage Range Pushbutton Switch:	Selects the full scale range of the AC/DC voltmeter. Always use the lowest range which will not over-range the meter.
AUX Voltage Selector Pushbutton Switch:	Used to select the circuit whose potential is to be measured by the AC/DC VOLTMETER. A description of each position follows:
DC:	Measures the DC Voltage output of the AUX Section at the AC/DC output binding posts.
AC:	Measures the AC Voltage output of the AUX Section at the AC/DC output binding posts.
EXT. AC:	Used to measure an external AC potential applied to the Red and Black binding posts on the BACK PANEL.
EXT. DC:	Used to measure an external DC potential applied to the Red and Black binding posts on the BACK PANEL.
NORMAL/DROPOUT Switch:	Used to perform a dropout timing test on an AC or DC auxiliary relay. When the switch is changed from the NORMAL to the DROPOUT position, the relay under test is de-energized and the digital timer is simultaneously started, provided the operator has preset the TIMER CONTROL selection to the V.RLY/DO position.
SOURCE NORMAL/EXTERNAL Switch:	Selects whether the AUXILIARY OUTPUTS variable autotransformer is energized from an internal (NORMAL) or an external source. When it is desirable to energize from an external source of power (not over 120 volts AC) such as a phase shifter or frequency generator, the source is connected to the Yellow and White ($\pm$) binding posts. The potential is then controlled by the AUXILIARY OUTPUTS knob.

**AUX INITIATE
NORMAL/BYPASS**

Switch:

This switch is used in conjunction with the AUX. OUTPUT in order to utilize Unit #2 in conjunction with Unit #1, or as a stand alone unit. When in the NORMAL position, output can be obtained from initiating Unit #1. When in the BYPASS position Unit #2 is initiated and the AUX AC/DC Voltage outputs can be adjusted from the AUXILIARY Section of Unit #2.

NOTE: The center position of this switch is the OFF position, when using Unit #2 interconnected to Unit #1 the switch should be in the NORMAL position. When using Unit #2 as a stand alone unit the switch should be in the CENTER or OFF position and switched from OFF to BYPASS to initiate the AUXILIARY Section of Unit #2.

**IR TEST Switch and
Output Pins:**

Used in conjunction with the VOLTAGE Selector Switch and AUX ADJUST Control knob, the AUX voltmeter, and the AUX Voltmeter range switch.

The IR TEST is first setup by depressing the bottom switch of the VOLTAGE Section until a red LED is illuminated adjacent to the position IR. The AUX ADJUST Control knob is used to calibrate the Megohm range on the AC/DC voltmeter to the infinity calibration mark with the SET/TEST Switch in the SET position. In the TEST position, 500 volts DC is applied and the insulation resistance is indicated on the AC/DC voltmeter. The output is available at the small Red (+) and Black (-) output pins.

UNIT #2 - BACK PANEL

Fuses - 115V, [230V]

F1 - 1.5A, [0.5A]	Protects the input line filter from abnormal current surges and short-circuits.
F2 - 3A, [1.5A]	Provides protection for the AUX ADJUST output transformer and the wiper arm of the AUX ADJUST variable transformer.
F3 - 8A, [5A]	Protects the 0 to 25A, 0 to 300V, or 0 to 600V AC output channel.
F4 & F5 - 5A, [2A]	Provides protection to Unit #2 when an EXTERNAL AC/DC Voltage is injected into the test set.
F6 & F7 - 15A, [7A]	Provides overload and short-circuit protection for the test set and is connection to either Unit #1, or the users AC voltage distribution outlet.
F8 - 5A, [5A]	Protects the diode circuitry necessary for generating the half wave rectified DC current in conjunction with the Harmonic Restraint Switch.

EXT. INPUT POWER: These two binding posts, yellow and white, with white being the instantaneous (+/-) polarity terminal, are to be used in conjunction with the Source External/Normal Switch. These binding posts are used, when it is desirable to energize Unit #2 of the SR-90 from an external source of power such as a frequency generator or a phase shifter.

INPUT LINE RECEPTACLE: A three-prong CSA, IEC, and UL approved receptacle is provided for connection of Unit #2 to Unit #1.

POWER ON/OFF SWITCH: This toggle switch is provided to initially turn the test set on to eliminate any confusion regarding the use of INITIATE CONTROL circuitry in either the NORMAL or BYPASS mode of operation.

GND. POST: This binding post is necessary to establish a common grounding point in addition to the ground supplied by the INPUT LINE CORD between Unit #2 and Unit #1.

UNIT #1 INTERCONNECT RECEPTACLE: This 14 pin receptacle is provided to interconnect Unit #2 with Unit #1 in order to gain complimentary circuitry as noted in this manual.

SELECTION OF OUTPUT TAPS

Unit #1 has several output terminals at various voltage and current ratings provided to adapt the SR-90 to a wide variety of test circuit impedances. The test set works at its peak efficiency when the outputs are used at or slightly above their ratings, (for overload capability see page 19). In this way, finer adjustment can be obtained by making maximum use of the variable auto transformer. The LOWER CURRENT terminals should be used when testing high impedance devices, where the rated current terminals do not have sufficient voltage to "push" the desired test current through the relay under test, without waveform distortion, use the next LOWER CURRENT terminal to avoid waveform distortion by doubling the voltage and having twice the voltage to "push" up to three times the rated output of current.

IT SHOULD BE NOTED THAT THERE IS NO RELATIONSHIP BETWEEN THE AMMETER RANGES AND THE CURRENT TAPS. ANY AMMETER RANGE CAN BE USED ON ANY TAP.

SERVICE DATA

Multi-Amp Model SR-90 uses straight forward circuits and components requiring little or no routine servicing except for cleanliness.

The following maintenance is recommended:

1. Open the unit every six months and examine for:
 - a. Dirt
 - b. Moisture
 - c. Corrosion
 - d. Condition of relay contacts
2. Remove dirt with dry compressed air.
3. Remove moisture by opening unit as much as possible and putting it in a warm dry environment.
4. As corrosion may take many forms, no specific recommendations can be made for its removal.

If factory service is required or desired, contact the factory for return instructions.

A Return Authorization (RA) number will be assigned for proper handling of the unit when it arrives at the factory.

If desired, a letter with the number and instructions can be provided.

Provide the factory with model number, serial number, nature of the problem or service desired, return address, your name, and where you can be reached should the factory need to contact you.

A purchase order number, cost limit, billing, and return shipping instructions may also be provided if desired.

National Institute of Standards and Technology recommends traceable calibration and certification once a year. Calibration and certification of two types is available if desired at an additional cost.

CLASS ONE: A certificate is provided verifying the traceability and calibration of the equipment.

CLASS N: That which is required for nuclear power plants. A certificate of traceability and calibration along with "as found" and "as left" data are provided.

If an estimate is requested, provide the name and contact information of the person with approval/disapproval authority.

Pack the equipment appropriately to prevent damage during shipment. If a reusable crate or container is used, the unit will be returned in it if in suitable condition.

Put the RA number on the address label of the shipping container for proper identification and faster handling.

WARRANTY

Multi-Amp Corporation warrants to the original purchaser that the product is free of defects in material and workmanship for a period of one (1) year from date of shipment. This warranty is limited and shall not apply to equipment which has damage, or cause of defect, due to accident, negligence, improper operation, faulty installation by the purchaser, or improper service or repair by any person, company or corporation not authorized by Multi-Amp Corporation.

Multi-Amp Corporation will, at its option, either repair or replace those parts and/or materials that it deems to be defective. Any costs incurred by the purchaser for the repair or replacement of such parts and/or materials shall be the sole responsibility of the original purchaser.

THE ABOVE WARRANTY IS IN LIEU OF ALL OTHER WARRANTIES, EITHER EXPRESSED OR IMPLIED ON THE PART OF THE MULTI-AMP CORPORATION, AND IN NO EVENT SHALL THE MULTI-AMP CORPORATION BE LIABLE FOR THE CONSEQUENTIAL DAMAGES DUE TO THE BREACH THEREOF.

OVERLOAD CAPABILITY OF UNIT #1

The Model SR-90, Unit #1, incorporates five current output ranges which are designed to utilize the main output transformer's overload capability, provided the output voltage is sufficient to "push" the output current through the impedance of the load circuit. Where the output voltage is sufficient to "push" more than rated output current, each current range may be overloaded for short durations of time, in accordance with the table below. Fuse protection is incorporated to prevent overloading provided the proper fuse size is used and that the Minimum OFF times are observed to avoid the possibility of damaging the output transformer and/or the variable autotransformer. When the "ON" time is less than the times indicated below, the time "OFF" time can be proportionally reduced.

	<u>Current</u>	<u>Maximum Time ON</u>	<u>Minimum Time OFF</u>
<u>10-Volt, 140-Ampere Range</u>			
	140A	5 min.	30 min.
	280A	75 sec.	30 min.
	320A	30 sec.	30 min.
<u>20-Volt, 70-Ampere Range</u>			
	70A	5 min.	30 min.
	140A	75 sec.	30 min.
	210A	30 sec.	30 min.
<u>40-Volt, 35-Ampere Range</u>			
	35A	15 min.	30 min.
	70A	3 min.	8 min.
	105A	30 sec.	4 min.
<u>80-Volt, 17.5-Ampere Range</u>			
	17.5A	15 min.	30 min.
	35.0A	3 min.	8 min.
	50.0A	30 sec.	4 min.
<u>160-Volt, 8.75-Ampere Range</u>			
	8.75A	15 min.	30 min.
	17.5A	3 min.	8 min.
	25.0A	30 sec.	4 min.

OVERLOAD CAPABILITY OF THE 0-25 AMPERE OUTPUT OF UNIT #2

The 0 to 25 ampere output channel of Unit #2 has the capability of being overloaded at 37.5 amperes with a duty cycle of 5 minutes **ON** and 30 minutes **OFF**.

TESTING PROTECTIVE DEVICES WITH THE SR-90 TIMER

The following procedure outlines a generic and efficient manner to consecutively perform various tests with the TIMER on Unit #1 of the SR-90. There are literally hundreds of testing applications for the TIMER in the Model SR-90. There are 48 control function combinations and 3 timer mode selections. Once the operation of the TIMER is thoroughly understood, the operator can easily construct a test procedure for each application encountered. Various procedures could be suggested by Multi-Amp, but the correct method of timing various devices depends entirely on the recommendations of the manufacturer of the device and the preferences of the operator or the organization that establishes the standards for performing such tests.

General Test Procedure:

1. Connect the SR-90 to a suitable source of power.
2. Switch the POWER ON/OFF Switch to ON.
3. Switch the START Selector Pushbutton Switch to the desired position for the START function to be used.
4. When it is desired to use a separate STOP gate signal to stop the timer, switch the STOP Selector Switch to the desired position.
5. Switch the LATCHED Switch to the desired position for the START/STOP gates. If it is desired to use a separate STOP function to stop operation of the TIMER, switch the START LATCH ON. If it is desired to use the reversal of the START signal to stop the timer switch the START LATCH OFF.
6. Switch the SEC/CYCLES Switch to the desired position.
7. Make the necessary connections to the START and STOP/MONITOR binding posts.
8. When the appropriate START and STOP signals are applied, the display indicates the elapsed time of the test.

NOTE: Always RESET the TIMER before each timing test to assure all logic circuits are in the correct state, even when the display registers zero. This is especially recommended when any switch positions are changed.

TESTING INDUCTION DISC OVERCURRENT RELAYS

Westinghouse Type CO
General Electric Type IAC

The following procedure outlines the most efficient manner to consecutively perform all tests on an overcurrent relay. This procedure involves the least possible number of changes in connecting test leads and setting test set controls.

Always refer to the instruction book of the relay being tested to ascertain the manufacturer's recommendations for accuracy limits, adjusting procedures, etc.

Unit #1 of Model SR-90 can be used independently of Unit #2 for conducting all of the following tests:

Zero check

Pickup - Induction Unit

Timing - Induction Unit

DC Target and Seal-In

Pickup - Instantaneous Unit

SET-UP OF CONTROLS ON UNIT #1

CONTROL

POSITION

POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
MONITOR/HORN Switch	Either position
AC CONTROL Knob	"0"
DC/VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	Set to read test current in upper section of meter scale
DC or VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

ZERO CHECK

This test is usually performed on a new relay to determine that the relay contacts close when the time dial is set to zero. If an "As Found Test" is to be performed on the relay, do not perform the zero check.

1. Connect light leads from binding posts marked STOP/MONITOR to trip circuit contact terminals of the relay induction unit.
2. Manually rotate time dial on the relay toward zero until the continuity light glows or tone signal sounds. Record reading on time dial.
3. Adjust for any irregularities uncovered and return time dial to specified setting.

PICKUP - INDUCTION UNIT

This test is to determine the minimum operating current of the relay; that is, the minimum current needed to close the relay contacts for any particular tap setting. Most manufacturers specify that the pickup current should be equal to tap value $\pm$ 5%.

1. Connect induction unit operating coil of relay to the COMMON ($\pm$) and 17.5A terminals (use 8.75A terminal for ground relays, i.e., those with tap ranges of 0.5 - 2A).
2. Set AC AMMETER RANGE Switch so that the anticipated pickup current (relay tap value) will be read in upper 1/3 section of ammeter scale.
3. Initiate unit by pressing INITIATE Switch.
4. Rotate AC CONTROL knob (clockwise) to increase output until relay picks up and continuity light flickers or tone signal wavers. VERNIER control may be used for fine adjustment.
5. Read current on ammeter. Record.
6. Return both AC CONTROL knob and VERNIER Control knob to "0" and de-initiate test set.

TIMING TEST - INDUCTION UNIT

1. Set INITIATE CONTROL, MOM/MAINT switch to MOM.
2. Set AC AMMETER RANGE Switch so that test current will be read in upper section of meter scale.

NOTE: See AMMETER CIRCUIT section for instructions on use of CURRENT MEMORY.

3. Initiate unit by pressing INITIATE button.

4. Set desired test current by jogging unit with INITIATE Switch and rotating AC CONTROL knob (clockwise) to increase output until ammeter setting is reached. Hold in INITIATE Switch and rotate VERNIER control to make final current adjustment.

5. Set TIMER CONTROL to INITIATE position.

6. Reset TIMER to zero with RESET button.

7. Initiate unit by pressing INITIATE button. TIMER will count and test current will flow. The test set will automatically shut off and the timer will stop when relay operates.

NOTE: Check ammeter while test is on. Minor adjustment may be made with VERNIER control.

8. Read TIMER. Time shown is total time of test. Record time.

9. If it is desired to obtain another point of relay curve, reset TIMER and proceed from Step 2.

10. When test is concluded, return AC CONTROL knob and AC VERNIER to "0" and de-initiate test set.

TESTING DC TARGET AND SEAL-IN

1. Remove test leads from STOP/MONITOR binding posts and connect to $[\pm]$ DC binding posts.

2. Select proper range for DC ammeter with the DC AMMETER RANGE Switch.

3. Set DC/VERNIER Switch to DC.

4. Select proper range for AC ammeter so that a current of approximately 150% of the relay tap value may be read in the upper section of the meter scale.

5. Initiate test unit by pressing INITIATE button.

6. Rotate AC CONTROL knob clockwise to energize induction unit operating coil of relay with a current equal to approximately 150% of the tap value. This is simply to make the relay operate and complete the trip circuit.

7. When the induction unit trip circuit contacts of the relay close, slowly rotate the DC VERNIER control knob clockwise to energize target coil of relay with DC. When target drops, read and record DC amperes.

8. Rotate AC CONTROL knob counterclockwise to zero. If the DC circuit remains energized when the induction unit trip circuit contacts of relay open, the seal-in unit is working properly.
9. Gradually rotate the VERNIER control knob counterclockwise toward zero, when the target coil of the relay drops out to its normally open position read and record the DC amperes. This is the Drop Out value of the Target and Seal-in relay. Turn test set OFF.

TESTING INSTANTANEOUS PICKUP

1. Connect instantaneous unit operating coil of relay to the COMMON [$\pm$] and 140A terminal of test set.
2. Connect instantaneous unit trip circuit contacts of relay to the STOP/MONITOR binding posts of test set.
3. Set AC AMMETER RANGE Switch so that anticipated instantaneous test current will be read in upper section of meter scale.
4. Set DC/VERNIER Switch to VERNIER.
5. Set INITIATE CONTROL, MOM/MAINT switch to MOM.
6. Set CURRENT MEMORY/CONTINUOUS switch to MEMORY. Initiate unit by depressing the INITIATE switch.
7. Rotate AC CONTROL knob clockwise to increase current until the continuity light glows or tone signal sounds. Make sure this is minimum setting on the AC CONTROL where the instantaneous unit of the relay will consistently pickup as the INITIATE button is alternately opened and closed. The glowing of the continuity light or the tone signal should be simultaneous with the depression of the INITIATE button.
8. Rapidly read this value of current and release INITIATE button.

WARNING

CURRENT IS FLOWING THROUGH THE RELAY COIL UNTIL INITIATE BUTTON IS RELEASED.

9. Record ammeter reading.
10. Return all Control knobs to "0" and de-initiate test set.

TESTING OVER/UNDER VOLTAGE RELAYS
Westinghouse Type CV
General Electric Type IAV

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
TIMER CONTROL	V.RLY/DO
MONITOR/HORN Switch	Either position
AC CONTROL Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER/VOLTMETER Switch	200V
DC or AC VERNIER CONTROL Knob	"0"
DC AMMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

0-25A/0-600V Output Select Switch	0-300 V
AC VOLTMETER RANGE Switch	So that the desired test voltage will be read in upper 1/3 of scale.
AC INITIATE Switch	NORMAL.
AC ADJUST Control Knob	"0"
HARMONIC RESTRAINT/NORMAL Switch	NORMAL.
V. RELAY Switch	NORMAL.
AUX AC VOLTMETER CIRCUIT SELECTOR Switch	So that the desired test voltage will be read in upper 1/3 of scale.
AUX ADJUST Control Knob	"0"

AUX VOLTAGE Selector Switch	150V AC or 300V AC (depending on nominal operating voltage of the relay).
NORM./DROPOUT Switch	NORMAL.
SOURCE	NORMAL.
AUX INITIATE Switch	NORMAL.

TESTING FOR PICKUP

1. Connect the relay operating coil to the AC/DC OUTPUT, Red and Black binding posts of Unit #2 AUXILIARY Section.
2. Connect light leads from binding posts marked STOP/MONITOR of Unit #1, to the trip circuit contact terminals of the relay induction unit.
3. Set INITIATE CONTROL, MOM/MAINT to MAINT, on Unit #1.
4. Initiate test set by pressing the INITIATE Switch.
5. Rotate the AC ADJUST Control Knob, of Unit #2, (clockwise) to increase output until CONTINUITY light flickers or the TONE generator output breaks.
6. Record this value of voltage as pickup of the relay.

TESTING TIMING

UNIT #1

7. De-Initiate UNIT #1. Set TIMER CONTROL to V.RLY/DO position.

OPTIONAL: Select TIMER for 0.01 seconds, (default), 0.0001 seconds or cycles mode.

UNIT #2

8. Set AC INITIATE SWITCH to BYPASS and AUX INITIATE Switch to BYPASS.
9. Set V. RELAY Section switch to NORMAL, Voltage section defaults to AC and operator chooses 150V or 300V range.
10. Rotate the AC ADJUST Control Knob (clockwise) to increase output until normal relay voltage (see relay nameplate) is observed on voltmeter.

11. Switch the V. RELAY Test Switch to FAULT position.

--- 12. Set faulted relay voltage by rotating AUX ADJUST Control Knob to increase or decrease output. Read the fault voltage on the voltmeter.

NOTE: Set the fault voltage approximately one to two volts higher than the desired test voltage.

13. Switch the V. RELAY Test Switch to the TEST position. The fault voltage will be impressed on the relay operating coil and the digital timer will automatically start.

14. When the relay trip circuit contacts make, the timer will stop to indicate the elapsed time of the test.

15. If a retest is desired, return the V. RELAY Test Switch to NORMAL. Reset TIMER, and repeat Steps 9 through 14 for the other values of fault voltage.

TESTING DC TARGET AND SEAL-IN

16. The DC TARGET and SEAL-IN unit can be tested following the procedure given in the test procedures for testing an overcurrent relay.

TESTING PERCENTAGE DIFFERENTIAL RELAYS

Westinghouse Type CA
General Electric Type IJD

TYPES OF TESTS

Pickup
Time Current Characteristic
Through Fault
Slope

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
AC AMMETER RANGE Switch	So that the desired test current can be read in the upper 1/3 of the scale.
DC VERNIER/Switch	VERNIER
DC or AC VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
0-25A/0-600V AC Switch	0-25A
AC AMMETER RANGE Switch	So that the desired test current can be read in UPPER 1/3 of scale
AC ADJUST Control Knob	"0"
HARMONIC RESTRAINT/NORMAL Switch	NORMAL

NORMAL/EXT. POWER INPUT Switch	NORMAL
--- DROP OUT/NORMAL Switch	NORMAL
SOURCE Switch	NORMAL
AUX INITIATE Switch	NORMAL
AUX ADJUST Control Knob	"0"
NORMAL/DROPOUT	NORMAL
NORMAL/BYPASS	NORMAL

TESTING PICKUP

1. Connect the operating coil and one restraint coil of the relay to the 0-10V/140A terminal and the ($\pm$) COMMON.
2. Connect light leads from binding posts marked Stop/Monitor to Trip circuit terminals of the relay.

NOTE: These type relays usually have one moving contact and two fixed contacts. Use binding post terminals for one moving contact and one of the fixed contacts.
3. Set AC AMMETER RANGE Switch so that expected pickup current will be read in upper 1/3 of the ammeter scale.
4. Initiate test set by pressing INITIATE Switch.
5. Rotate AC CONTROL Knob to increase output until relay picks up and CONTINUITY light glows or the TONE generator sounds. The Vernier control knob may be used for fine adjustment. Read and record current.
6. Move one light lead to relay terminal for pickup of the other fixed contact of the relay and repeat test.
7. Return controls to "0" position and de-initiate test set.

TESTING TIME CURRENT CHARACTERISTICS

1. Set AC AMMETER RANGE Switch so that the desired test current can be read in upper 1/3 of the meter scale. Set CURRENT MEMORY/CONTINUOUS Switch to MEMORY.
2. Set INITIATE CONTROL knob to MOM.

3. Set test current by "jogging" with the INITIATE Switch and rotating the AC Current Control Knob of Unit #1 to increase the output until the ammeter indicates the desired test current.
4. Set INITIATE CONTROL to MAINT. and the TIMER CONTROL to the INITIATE position.
5. Reset TIMER by pressing the RESET button.
6. Initiate the test set by pressing the INITIATE Switch. The unit will energize and the Timer will begin to run. When the relay contacts close, the Timer will stop and the unit will de-energize itself.
7. Read and record time indicated on the Timer.
8. Return all controls to zero and de-initiate test set.

TESTING THROUGH FAULT

1. Connect the 0-25A binding posts of Unit #2 to the restraint current coil terminals of the relay, by a series connection of the restraint current coils. Observe polarity.
2. Select the proper ammeter range.
3. Set the INITIATE CONTROL MAINT. and the TIMER CONTROL to the INITIATE position.
4. Switch POWER ON/OFF Switch ON.
5. Initiate unit by pressing INITIATE Switch.
6. Rotate the AC ADJUST Control knob to increase output to desired value. Read current on ammeter.
7. Manually "turn" relay disc for evidence of restraint current.
8. Return control knob to zero and de-initiate test set.

TESTING SLOPE

1. Connect the operating coil and one restraint coil to the 17.5A output terminals of Unit #1. Observe polarity.
2. Select the proper ammeter ranges for both AC Ammeters.
3. Connect light leads from the binding posts marked STOP/MONITOR to the trip circuit terminals of the relay.

4. Set INITIATE CONTROL to MAINT.

5. Initiate the test set by pressing the INITIATE Switch.

6. Rotate the AC ADJUST Control knob of Unit #2 until the restraining current is obtained.

7. Rotate the AC CONTROL knob of Unit #1 until the CONTINUITY light flickers, or the HORN sounds. The slope of the relay is determined by dividing the operating current by the restraint current.

8. If desired, the test may be repeated for the opposite restraint coil by disconnecting test leads from the operating coil terminal and re-connecting test leads to opposite restraint coil terminal and operating coil terminal.

9. After test is completed, turn all controls to "0" and switch the POWER ON/OFF Switch OFF.

**TRANSFORMER DIFFERENTIAL RELAY WITH
PERCENTAGE AND HARMONIC RESTRAINT
General Electric Type BDD**

GENERAL

The Type BDD relay is a single-phase transformer differential relay provided with the features of percentage and harmonic restraint and has a sensitive polarized relay as the operating element. Percentage restraint permits accurate determination between internal and external faults at high currents. Harmonic restraint enables the relay to distinguish, by the difference in waveform, between the differential current caused by an internal fault and that caused by transformer magnetizing inrush.

The harmonic restraint and slope tests are written based on testing the relay with all restraint windings set in the 5A tap. If the relay is to be tested with any other tap settings, please refer to the G.E. instruction book under "Periodic Testing".

The Type BDD 15 relay is designed to be used for the protection of two-winding power transformers and has two (2) through-current restraint circuits and one (1) differential current circuit.

The Type BDD 16 relay is designed to be used with three-winding power transformers and has three (3) through-current restraint circuits and one (1) differential current circuit.

TYPES OF TESTS

Pickup of DHR Unit
Slope
Harmonic Restraint
Pickup of Instantaneous Unit

**ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING
SET-UP OF CONTROLS ON UNIT #1**

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
HORN/MONITOR Switch	Either position
INITIATE CONTROL	MAINT.
AC CONTROL Knob	"0"
AC AMMETER RANGE Switch	So that the desired AC current can be read in upper 1/3 meter scale

DC/OFF/VERNIER Switch	VERNIER
DC OR AC VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
0-25A/0-300V/0-600V AC Switch	0-25A
AC AMMETER RANGE Switch	25A
AC ADJUST Control Knob	"0"
HARMONIC RESTRAINT/NORMAL Switch	NORMAL
AC INITIATE Switch	NORMAL
AUX ADJUST Control Knob	"0"
AUX VOLTAGE Section	DC/150V
AUX VOLTMETER	DC
AUX INITIATE Switch	NORMAL
AUX VOLTMETER Selector Switch	200V
DROPOUT/NORMAL Switch	NORMAL
SOURCE Switch	NORMAL

INITIAL TEST CONNECTIONS

1.
 - a. 8.75A binding post on Unit #1 to terminal 5 of the relay.
 - b. 0-25A COMMON ($\pm$) binding post on Unit #2 to COMMON ($\pm$) binding post on Unit #1.
 - c. COMMON ($\pm$) binding post on Unit #1 to terminal 4 of the relay.
 - d. AUX DC VOLTAGE OUTPUT Binding Posts, of Unit #2, to terminal 1 and 7 of the relay. Red (+) to terminal 1.
 - e. STOP/MONITOR Binding Posts to terminals 1 and 2 of the relay.

2. Reset TIMER by pressing the RESET Pushbutton.
3. Initiate unit by depressing INITIATE Pushbutton.
4. Rotate AUX ADJUST Control Knob, of Unit #2, clockwise until rated DC voltage is indicated on the AUX DC Voltmeter.

NOTE: For the duration of the test, rated voltage will be present on the relay, whenever the test set is INITIATED.

TESTING PICKUP

5. Rotate AC CONTROL Knob of Unit #1 in a clockwise direction until an indication of pickup is detected by the CONTINUITY Lamp or TONE Generator. Read and record the value of pickup current observed on the AC AMMETER on Unit #1.
6. Return the AC Control Knob to "0".
7. Observe that the target element (T) "dropped" during the test.
8. Move test lead connected to COMMON ($\pm$) from terminal 4 to terminal 6 of the relay.
9. Rotate AC CONTROL Knob in a clockwise direction until an indication of pickup is detected by the CONTINUITY Lamp or TONE Generator. Read and record the value of pickup current observed on the AC AMMETER on Unit #1.
10. Return AC Control Knob to "0" and de-initiate test set.

TESTING SLOPE

11. Connect 0-25A current output Binding Post of Unit #2 to terminal 4 of the relay.
12. Place INITIATE CONTROL in the MOM. position.

WARNING

The relay coils are energized as long as the test set is initiated. Therefore, this test should be conducted as rapidly as possible to prevent damage to relay coils.

13. Preset and hold INITIATE Pushbutton, rotate AC ADJUST Control Knob until an indication of 20 amperes is observed on the AC AMMETER of Unit #2. Release INITIATE Pushbutton. Reset INITIATE CONTROL to the MAINT. position.

14. Set AC AMMETER Range Switch on Unit #1 to 20A position.
15. Set CURRENT/MEMORY Switch to MEMORY.
16. INITIATE test set and slowly rotate AC CONTROL Knob until pickup is detected by the AC CURRENT MEMORY circuit. Read value of current indicated on AC AMMETER on Unit #1.
17. Record value of current read in step 16.
18. Return AC ADJUST Control Knob to "0".
19. Return AC CONTROL Knob to "0" and de-initiate test set.

TESTING HARMONIC RESTRAINT

20. Place INITIATE CONTROL in the MAINT. position.
21. Place AC AMMETER Range Switch on Unit #2 in the 25A position.
22. Place DC AMMETER Range Switch on Unit #1 in the 5A position.
23. Place the HARMONIC RESTRAINT Switch in the HARMONIC RESTRAINT position.
24. Move the test lead from the 0-25A output (blue) binding posts from terminal 4 of the relay to terminal 5 of the relay.
25. Initiate test set by pressing INITIATE Pushbutton.
26. Rotate AC ADJUST Control Knob of Unit #2 clockwise until an indication of 4 amperes DC is observed on the DC AMMETER on Unit #1.
27. Rotate AC CONTROL Knob until pickup is detected by the CONTINUITY Lamp or TONE Generator. Read and record the value of current indicated by the AC AMMETER on Unit #1.

NOTE: While adjusting the AC CONTROL Knob of Unit #1, make necessary adjustments using AC ADJUST Control Knob of Unit #2 to maintain 4 amperes DC on the DC ammeter of Unit #1.

28. Return the AC CONTROL Knob to "0".
29. Return the AC ADJUST Control Knob to "0".
30. Return DC VERNIER Control Knob to "0".

TESTING INSTANTANEOUS UNIT

31. Set INITIATE CONTROL in the MOM. position.
32. Disconnect test lead of Unit #2 0-25A output (blue) binding post from the relay.
33. Set AC AMMETER RANGE Switch on Unit #1 to 200A position.
34. Connect test leads from Unit #1 to terminals 5 and 6 of the relay.
35. Initiate unit by holding in INITIATE Pushbutton.

NOTE: Steps 35 and 36 should be performed as quickly as possible to avoid relay damage. The preferred method is to reference back to the AC CURRENT MEMORY/CONTINUOUS FUNCTION OF UNIT #1.

36. Rotate AC CONTROL Knob clockwise to increase current until pickup is detected by the CONTINUITY Lamp or TONE Generator.
37. Read the value of current on the AC AMMETER on Unit #1 and release the INITIATE Pushbutton.
38. Record value of current observed in Step 37.
39. De-initiate test set and remove all test leads.

TYPICAL TEST FOR DC AUXILIARY RELAYS

TYPES OF TESTS

Pickup
Dropout
Timing Dropout

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
HORN/MONITOR Switch	Either position
INITIATE CONTROL	MAINT.
TIMER CONTROL	INITIATE
AC CONTROL Knob	"0"
AC AMMETER RANGE Switch	20A
DC/VERNIER Selector Switch	OFF
DC or AC VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
0-25A/0-300V/0-600V Switch	0-25A
AC INITIATE Switch	NORMAL
AC ADJUST Control Knob	"0"
VOLTMETER RANGE Switch	So that the desired test current can be read in UPPER 1/3 of scale
HARMONIC RESTRAINT/NORMAL Switch	NORMAL
SOURCE Switch	NORMAL

NORMAL/DROP OUT Switch	NORMAL
AUX INITIATE Switch	NORMAL
AUX VOLTAGE SELECTOR Switch	DC; Either 150V or 300V
AUX VOLTMETER SELECTOR Switch	DC; Either 200V or 500V
AUX ADJUST Control Knob	"0"

TESTING PICKUP

1. Connect the operating coil terminals of the relay to the AUX AC/DC OUTPUT Red (+) and Black (-) binding posts of the AUX OUTPUT section of Unit #2.
2. Connect light leads from binding posts marked STOP/MONITOR, of Unit #1, to trip circuit contact terminals of the relay.
3. Initiate unit by pressing INITIATE Switch.
4. Rotate AUX ADJUST Control knob clockwise to increase output until CONTINUITY light flickers or TONE generator sounds.
5. Read pickup voltage on voltmeter. Record.
6. Rotate AUX ADJUST Control knob counterclockwise to decrease output until CONTINUITY light extinguishes or output from TONE generator breaks.
7. Read dropout voltage on voltmeter. Record.

TESTING DROPOUT TIME

8. Set INITIATE CONTROL to MAINT. and TIMER CONTROL to V.RLY/DO. Set STOP GATE to N.C. DRY CONTACTS.
9. Rotate AUX ADJUST Control Knob clockwise until rated voltage is applied to relay.
10. Manually close the relay trip circuit contacts so that the DC contacts will pickup and seal-in. Release the relay trip contacts. The DC contacts should stay sealed in.
11. RESET digital timer.
12. Switch NORM/DROPOUT Switch to the DROPOUT position. The DC voltage is switched OFF and the TIMER is automatically initiated. When the DC contacts dropout, the timer will stop. Read and record this value.
13. Return AUX ADJUST Control Knob to "0" position and switch POWER OFF.

TESTING INSULATION RESISTANCE

NOTE: NEVER PERFORM AN INSULATION RESISTANCE TEST ON A SOLID STATE OR STATIC RELAY.

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
AUX INITIATE Switch	Center Pos.
0-25A/0-300V/0-600V Output Select Switch	0-300V AC
AC AMMETER RANGE Switch	25A
AC INITIATE Switch	NORMAL
AC ADJUST Control Knob	"0"
HARMONIC RESTRAINT/NORMAL Switch	NORMAL
SOURCE SELECTOR Switch	NORMAL
AUX VOLTAGE RANGE SELECTOR Switch	500V
AUX ADJUST Control Knob	"0"
AUX IR TEST Switch	OFF
NORMAL/DROPOUT Switch	NORMAL

TESTING

1. Connect Model SR-90 to a suitable source of power. Be sure the AUX INITIATE Switch is OFF, in the center position.
2. Switch the AUX INITIATE to BYPASS, turning Unit #2 test set ON.
3. Set AUX VOLTAGE Switch to IR.
4. Initiate IR TEST by depressing INITIATE Switch of IR TEST. The insulation resistance test circuit light, ON/SET, should glow.
5. Rotate AUX ADJUST Control Knob to increase output to 500 volts DC, as indicated on the AUX DC VOLTMETER.
6. Set AUX VOLTMETER RANGE SELECTOR Switch to the Megohm range as indicated by the symbol M(Ω).
7. Connect high voltage test probes to the output terminals and to the relay under test. The relay components will not be harmed as long as one probe is applied to relay frame and the other to all external terminals of the relay.
8. Switch IR TEST Switch to TEST position. 500 volts DC is now applied to the relay and the insulation resistance can be read on the megohm scale of the voltmeter.
9. Return AUX ADJUST Control knob to "0" and switch, main power, AUX INITIATE to center position OFF.

TESTING I.T.E. CIRCUIT SHIELD SOLID-STATE OVERCURRENT RELAYS

The following procedure outlines the most efficient manner to consecutively perform all tests on an I.T.E. solid state overcurrent relay. This procedure involves the least possible number of changes in the connecting of test leads and setting of test controls.

TYPES OF TESTS

Pickup - Timing Circuit
Time Delay Test
Instantaneous Pickup Test
DC Target - Timing Circuit
DC Target - Instantaneous Circuit

CAUTION

NEVER FEED VOLTAGE INTO THE N.O. or N.C. DRY CONTACT
CIRCUIT MODEL SR-90. ALWAYS USE THE VOLTAGE APPLIED
CONTACT MONITOR CIRCUIT OF THE MODEL SR-90. OTHERWISE
DAMAGE WILL OCCUR TO THE SOLID-STATE COMPONENTS OF
THE SR-90 AS WELL AS TO THE RELAY.

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MOM.
TIMER CONTROL	INITIATE
MONITOR/HORN Switch	Either position
DC VOLTMETER RANGE Switch	150V
DC or VERNIER Control Knob	"0"
AC AMMETER RANGE Switch	To read test current in the upper 1/3 of meter scale.
AC CONTROL Knob	"0"
DC or VERNIER/Switch	DC

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
0-25A/0-300V/0-600V AC Switch	300V AC
0-25A or 0-300V AC ADJUST Knob	"0"
VOLTMETER RANGE Switch	150V

PICKUP- TIMING CIRCUIT

1. Connect relay input circuit (relay terminals 1-2, 3-4, or 5-6) to the binding posts of Unit #1. It is recommended that the (0-80V) @ 17.5A output tap be used and for the 0.5 to 2.0 amp relays, it is recommended to use the (0-160V) @ 8.75A output tap.
2. Connect a pair of light leads from the binding posts marked STOP/MONITOR to terminals 8 and 12. Select the STOP GATE for VOLTAGE APPLIED mode of operation.
3. Select the AC AMMETER RANGE Switch so that the relay's tap value of current may be read on the upper 1/3 of the ammeter scale.
4. Connect a pair of leads from the Red and Black binding posts of the DC OUTPUT Section, of Unit #1, to terminals 7 and 8 with Black ($\pm$) post to terminal 8. Select the required DC VOLTAGE RANGE of either 150V or 300V.
5. INITIATE the test set by pressing and holding the INITIATE pushbutton.
6. Rotate DC VERNIER knob, on Unit #1, until rated DC logic voltage is read on the voltmeter.
7. Rotate AC CONTROL knob to increase output until test current on relay is (-5%) of tap value.
8. Release the INITIATE pushbutton, de-energizing the test set.
9. Set INITIATE CONTROL to MAINT. and reset TIMER. Initiate test set by pressing INITIATE Switch. Relay input circuit will "see" test current. Relay should not operate. De-energize the test.
10. Repeat Steps 5 through 9 above, except test current should be set at relay tap value (+5%).
11. Initiate test set by pressing INITIATE Switch. Relay input circuit will "see" test current. Relay should operate.

TIME DELAY AND TARGET TEST

1. Set INITIATE CONTROL to MOM.
2. Select AC AMMETER/VOLTAGE RANGE Switch so that desired test current may be read on the upper 1/3 or ammeter scale.
3. Set the AC CURRENT SELECTOR to MEMORY and to the desired test current.
4. Increase test current by "jogging unit" with INITIATE Switch and rotating AC CONTROL knob to increase output until desired test current is indicated by the ammeter. Release INITIATE Switch.
5. Set INITIATE CONTROL to MAINT and reset timer by pressing the reset button.
6. Initiate unit by pressing INITIATE Switch. TIMER will initiate and test current will be indicated on ammeter. The test set will automatically de-initiate and the TIMER will stop when relay's contacts close. Relay target should operate.

INSTANTANEOUS PICKUP AND TARGET TEST

1. Set INITIATE CONTROL to MOM.
2. Relay terminal connections will be the same as for the above tests except jumper terminals 9 and 10.
3. Select an AC AMMETER RANGE so that desired test current may be read on the upper 1/3 of ammeter scale.
4. Initiate unit by pressing and holding INITIATE Switch. Rotate AC CONTROL Knob to increase current output until test current on relay is (-10%) of instantaneous setting. [For 0.5 to 2.0 ampere tap range, the setting should be (-20%)].
5. Release INITIATE Switch. Reset TIMER.
6. Press and hold INITIATE Switch. Relay instantaneous circuit should-not pickup to stop timer (allow approximately 0.30 seconds).
7. Repeat Step 4, except test current should be (+ 10%) of relay instantaneous setting. [For 0.5 to 2.0 ampere tap range, the settings should be (+ 20%)].
8. Press and hold INITIATE Switch. Relay instantaneous circuit should pick-up and stop the timer. Relay target should operate.
9. Release INITIATE Switch.

WARNING

CURRENT INDICATED ON AMMETER IS PRESENT IN RELAY CIRCUIT UNTIL INITIATE SWITCH IS RELEASED: THEREFORE, IT IS IMPORTANT TO PERFORM THIS TEST AS RAPIDLY AS POSSIBLE TO AVOID OVERHEATING RELAY.

10. Turn POWER ON/OFF Switch OFF.

DIRECTIONAL OVERCURRENT RELAY

Westinghouse Type CR
General Electric Type IBC

GENERAL

A Directional Overcurrent Relay trips a circuit when it senses two abnormal conditions in the following sequence:

1. Current flow must be reversed.
2. The reversed current flow must be higher than a prescribed amount, and the flow must continue for a predetermined time.

This relay is composed of two units, a directional unit and an overcurrent unit. The directional unit is similar to a single phase wattmeter. It contains a voltage actuated and current actuated coil. When these two coils are energized, a torque is produced on the unit's disc. A 180° shift in phase relationship between the voltage and current produces a reverse torque on the disc. Normally, the torque produced holds the directional unit contacts open. When the current flow in the circuit reverses, the directional unit contact will close.

The overcurrent unit of the relay is similar to the time delay overcurrent relay. In modern designs, the directional unit contacts must be closed before operating torque will be produced on the induction disc of the overcurrent unit. Thus, the directional overcurrent relay requires reversal as well as a minimum quantity of current flow before it may operate to trip a breaker.

The test procedure is arranged to test each element of the relay individually. The directional element contacts must be blocked, closed, or bypassed to permit complete testing of the overcurrent element.

TYPES OF TESTS

Directional Unit - Minimum Pickup
Overcurrent Unit

1. Minimum pickup
2. Time current characteristics

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS ON UNIT #1

CONTROL

POSITION

POWER ON/OFF Switch

ON

INITIATE CONTROL

MAINT.

HORN/MONITOR Switch	Either position
AC Control Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	200A
DC or AC VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
0-25A/300V/0-600V Output Select Switch	0-25A
AC AMMETER RANGE Switch	25A
AC ADJUST Knob	"0"
VOLTMETER RANGE Switch	1.5V
AC INITIATE Switch	NORMAL
AUXILIARY Adjust Control Knob	"0"
AUX. INITIATE Switch	NORM.
D.E.T. Switch	RATED setting per manual instruction leaflet
NORMAL/DROPOUT Switch	NORMAL

DIRECTIONAL UNIT MINIMUM PICKUP

1. Connect polarity terminal ($\pm$) of relay directional unit's current operating coil to the polarity terminal (Black $\pm$) of the AC/DC OUTPUT section of Unit #2. The other relay current operating coil terminal should be connected to the (Blue) binding post of the 0-25A section of Unit #2.
2. Connect the polarity ($\pm$) terminal of the relay voltage polarity coil to the (Red) binding post of the AC/DC OUTPUT section of Unit #2.
3. Place a jumper from the non-polarity terminal of the voltage polarizing coil to the polarity ($\pm$) terminal of the current polarizing coil on the relay.

4. Switch D.E.T. selector switch to desired test position.
5. Reset the TIMER and initiate the test set by pressing the INITIATE Button.
6. Rotate AC ADJUST Control knob of Unit #2 clockwise to increase output until directional unit contacts close. Reduce output just until the contacts start to open. Read and record values.

NOTE: CURRENT AMPLITUDE will be displayed on ammeter and
VOLTAGE Amplitude will be displayed on AUX. VOLTMETER.

7. Reverse leads from test set to simulate 180 degree phase shift. Relay directional unit contacts should resist contact closure.

TESTING PICKUP AND TIMING OF OVERCURRENT UNIT

1. Block directional unit contacts closed and follow procedure for Induction Disk Overcurrent Relay.

NOTE: AT END OF TEST REMOVE ALL BLOCKING MATERIAL

VOLTAGE RESTRAINT OVERCURRENT RELAY

General Electric Type IJCV

GENERAL

The IJCV contains an induction disc which is influenced by the magnetic fields of two electromagnets. The current actuated electromagnet produces torque on the disc to close the relay trip circuit contacts and is known as the operating coil. The potential actuated electromagnet produces torque on the disc to open the relay trip circuit contacts and is known as the restraint coil. When the voltage applied to the restraint coil is decreased, a smaller amount of current is required to operate the relay and close the trip circuit contacts. This relay may operate to close trip circuit contacts even though the voltage applied to the restraint coil may remain at full system voltage.

The IFCV relay is normally used to protect a generator against bus faults.

TYPES OF TESTS

Pickup of Overcurrent Unit, Zero Voltage Restraint
Pickup of Overcurrent Unit, System Voltage Restraint
Timing of Overcurrent Unit, Zero Voltage Restraint
Timing of Overcurrent Unit, System Voltage Restraint

ALWAYS REFER TO MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	So that desired test current may be read on upper 1/3 of meter scale
DC or AC VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

TESTING FOR PICKUP - ZERO VOLTAGE RESTRAINT

1. Connect the relay voltage restraint coil terminals to the Red and Black binding posts, labeled AC/DC OUTPUT on unit #2.
2. Connect the relay current operating coil terminals to Unit #1, 17.5A output terminal and the return to COMMON ($\pm$).
3. Connect a set of light leads from the relay trip circuit contact terminals to the test set's STOP/MONITOR binding posts.
4. INITIATE Unit by pressing INITIATE Switch.
5. Increase current through the current operating coil of relay to a value 50% above relay trip setting by rotating AC CONTROL knob clockwise.
6. When relay contacts close, CONTINUITY light should glow or TONE Generator should sound.
7. Slowly decrease current by rotating the AC CONTROL knob counterclockwise until CONTINUITY light flickers, or TONE breaks. Record this value of current as "Pickup - Zero Voltage Restraint".
8. Return AC CONTROL knob to "0" and de-initiate test set.

TESTING FOR PICKUP - SYSTEM VOLTAGE RESTRAINT

1. Repeat Steps 1 through 4 for TESTING FOR PICKUP - ZERO VOLTAGE RESTRAINT.
2. Apply system voltage to voltage restraint coil of relay by rotating the AUX ADJUST Control Knob (clockwise).
3. Repeat steps 5 through 8 for TESTING FOR PICKUP - ZERO VOLTAGE RESTRAINT and record "Pickup - System Voltage Restraint".

TESTING TIMING - OVERCURRENT UNIT - ZERO VOLTAGE RESTRAINT

1. Connect the relay voltage restraint coil terminals to the Red and Black binding posts, labeled AC/DC OUTPUT on unit #2.
2. Connect the relay current operating coil terminals to Unit #1, 17.5A output terminal and the return to COMMON ($\pm$).
3. Connect a set of light leads from the relay trip circuit contact terminals to the test set's STOP/MONITOR binding post.
4. Set INITIATE CONTROL to MOM.

5. Preset AMMETER to MEMORY position and set the desired test current.
6. De-initiate the test set by releasing the initiate button. Reset timer.
7. Set initiate control to maint.
8. Initiate unit by pressing INITIATE SWITCH. TIMER will initiate and test current will flow until the relay trip circuit contacts close.
9. Read TIMER and record time. Time shown is total time of test.

TESTING TIMING - OVERCURRENT UNIT - SYSTEM VOLTAGE RESTRAINT

1. Repeat Steps 1 through 6 for TESTING TIMING - OVERCURRENT UNIT - ZERO VOLTAGE RESTRAINT.
2. Rotate AUX ADJUST Control Knob (clockwise) to increase voltage until equal to relay system voltage.
3. Initiate unit by pressing INITIATE SWITCH. TIMER will initiate and test current will flow until the relay trip circuit contacts close.
4. Record time shown as "Overcurrent Timing Test with System Voltage Applied".

VOLTAGE CONTROLLED OVERCURRENT RELAY

Westinghouse Type COV

GENERAL

The COV relay contains an induction disc overcurrent unit and instantaneous undervoltage unit. The undervoltage unit supervises the operation of the overcurrent unit. Regardless of the amount of current passing through the operating coil of the overcurrent unit, no operation takes place unless the undervoltage unit has "dropped out". This means that the overcurrent unit may be set to operate on less than full load current when the voltage falls below a predetermined value. Conversely, the overcurrent unit will not operate as long as the voltage is above the predetermined value.

This relay is normally used to protect a generator against a bus fault.

TYPES OF TESTS

Pickup - Undervoltage Unit

Dropout - Undervoltage Unit

Voltage Control of Overcurrent Unit

Pickup - Overcurrent Unit

Time Current Characteristics - Overcurrent Unit

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
DC or VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	Desired Position
DC or VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
VOLTMETER RANGE Switch	So that the desired test voltage will be read in upper 1/3 of scale
SOURCE Switch	NORMAL
VOLTMETER CIRCUIT SELECTOR Switch	AC
AUXILIARY OUTPUT Control Knob	"0"
VOLTAGE OUTPUT Selector Switch	150V AC or 300V AC (depending on nominal operating voltage of the relay)
NORMAL/DROPOUT Switch	NORMAL
AUX INITIATE Switch	NORMAL

TESTING PICKUP AND DROPOUT OF UNDERVOLTAGE UNIT

1. Connect the Red and Black binding posts of Unit #2, AC/DC OUTPUT, to the undervoltage unit operating coil terminals.
2. Connect a pair of light leads from the STOP/MONITOR binding posts of the test set to the relay undervoltage unit contact terminals.
3. Initiate the test set by pressing the INITIATE CONTROL Switch.
4. Rotate the AUX ADJUST Control knob (clockwise) to increase voltage applied to the undervoltage unit operating coil until the continuity light just goes out. Read and record this value of voltage as the pick-up voltage of the undervoltage unit.
5. Continue to rotate AUX ADJUST Control knob clockwise to increase applied voltage until relay rated voltage is read on the test set voltmeter.
6. Rotate the AUX ADJUST Control knob counterclockwise to decrease applied voltage until the Continuity light first lights. Read and record this voltage value as the drop out voltage of the undervoltage unit.
7. Return AUX OUTPUT Control knob to "0" and de-initiate the test set.

TESTING VOLTAGE CONTROL OF OVERCURRENT RELAY

1. Connect the Unit #2, AC/DC OUTPUT, Red and Black binding posts to the undervoltage unit operating coil terminals.

2. Connect the AC Current output terminals of Unit #1 to the overcurrent operation coil terminals.
3. Adjust the AC AMMETER Range Switch so that the desired test current may be read on the upper 1/3 of the meter scale.
4. Connect a set of light leads from the STOP/MONITOR binding posts to the relay trip circuit contact terminals.
5. Press the timer reset button and initiate the test set by pressing the INITIATE CONTROL Switch.
6. Rotate AUX ADJUST Control knob clockwise until relay rated voltage is read on the voltmeter.
7. Rotate the AC CONTROL Knob clockwise until the value of current read on the AC AMMETER is approximately four times tap value of the overcurrent unit.
8. The overcurrent unit should not operate to close the relay trip circuit contacts.
9. Rotate the AUX ADJUST Control knob counterclockwise to reduce the voltage until the undervoltage unit drops out.
10. The overcurrent unit should operate to close the relay trip circuit contacts. This will stop the timer and de-energize the test set. There is no need to record the time indicated on the TIMER, this not the timing set.

TESTING PICKUP AND TIMING OF THE OVERCURRENT UNIT

1. Insure that the undervoltage contacts are closed before conducting tests.
2. Follow the test procedures for testing an overcurrent relay.

**TRANSFORMER DIFFERENTIAL RELAY WITH
PERCENTAGE AND HARMONIC RESTRAINT
Westinghouse Type HU**

GENERAL

The Type HU relay is a single-phase transformer differential relay provided with the features of percentage and harmonic restraint and has a sensitive polarized relay as the operating element. Percentage restraint permits accurate determination between internal and external faults at high currents. Harmonic restraint enables the relay to distinguish, by the differences in waveform, between the differential current caused by an internal fault and that caused by transformer magnetizing inrush.

The Type HU relay is designed to be used for the protection of two-winding power transformers and has two (2) through-current restraint circuits with one (1) differential current circuit.

The Type of HU-1 relay is designed to be used with three-winding power transformers and has three (3) through-current restraint circuits and one (1) differential current circuit.

TYPE OF TESTS

Pickup
DC Target
Slope
Harmonic Restraint
Instantaneous Unit

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either Position
AC CONTROL Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	20A
DC or AC VERNIER Control Knob	"0"

SET-UP OF CONTROLS ON UNIT #2

HARMONIC RESTRAINT/NORMAL Switch	NORMAL
OUTPUT SELECT Switch	0-25A
AC AMMETER RANGE Switch	25A
AC ADJUST Knob	"0"
AC INITIATE Switch	NORMAL
VOLTAGE SELECTOR Switch	DC/150 V
AUX ADJUST Control Knob	"0"
NORMAL/DROPOUT Switch	NORMAL
AUX INITIATE Switch	NORMAL

INITIAL TEST CONNECTIONS

1. a. 8.75A current output binding post on Unit #1 to terminal 3 of the relay.
- b. COMMON ($\pm$) binding post on Unit #1 to the 0-25A COMMON ($\pm$) binding post on Unit #2.
- c. COMMON ($\pm$) binding post on Unit #1 to terminal 7 of the relay.
- d. 0-25A (Blue) binding post on Unit #2 to terminal 5 of the relay.
- e. STOP/MONITOR binding posts to terminals 1 and 10 of the relay.

TESTING PICKUP

2. Block relay contact on the harmonic restraint unit closed.
4. Reset TIMER by pressing RESET Pushbutton.
5. Initiate unit by pressing INITIATE Pushbutton.
6. Rotate AC CONTROL Knob in a clockwise direction until an indication of pickup is detected by the CONTINUITY Lamp or TONE Generator. Read and record the value or pickup current observed on the AC AMMETER of Unit #1.
7. Return AC CONTROL Knob to "0" and de-initiate test set.

TESTING DC TARGET AND SEAL-IN

8. Place DC/OFF/VERNIER Switch to the DC Position.
9. Rotate AC CONTROL Knob in a clockwise direction until an indication on the AC AMMETER on Unit #1 of the value recorded for pickup plus 0.5 amperes is obtained.
10. Rotate DC Vernier Knob in a clockwise direction until the Target and Seal-In unit operates and the target "drops". Read and record value of current observed on DC AMMETER.
11. Return AC CONTROL Knob to "0". Observe DC AMMETER to verify that DC current continues to flow, through the DC target and seal-in coil.
12. Reduce the DC Vernier Knob until a drop out value is indicated by the releasing of the DC seal-in coil. Record this value.
13. De-initiate test set.

TESTING SLOPE

14. INITIATE UNIT by pressing INITIATE Pushbutton.
15. Set AC AMMETER Range Switch on Unit #2 to 25A position.
16. Rotate AC ADJUST Knob until 10 amperes AC is indicated by the AC AMMETER on Unit #2.
17. Set CURRENT MEMORY/CONTINUOUS switch on Unit #1 to MEMORY.
18. Slowly rotate AC CONTROL Knob of Unit #1 until pickup is indicated by the de-initiation of the test set through the CURRENT MEMORY control circuitry or by the CONTINUITY Lamp or TONE Generator. Read and record this value.
19. Return AC ADJUST Knob to "0".
20. Return AC CONTROL Knob to "0" and de-initiate test set.

TESTING HARMONIC RESTRAINT

21. Remove blocking on harmonic restraint unit and block differential unit contacts closed.
22. Place the HARMONIC RESTRAINT Switch in the HARMONIC RESTRAINT position. Connect the 0-25A (Blue) binding post on Unit #2 to terminal 3 of the relay.

23. This step is no longer needed, proceed to Step 24.
24. Set AC AMMETER RANGE Switch on Unit #1 to the 20A position.
25. Set AC AMMETER RANGE Switch on Unit #2 to the 25A position.
26. Rotate AC ADJUST Control Knob clockwise until an indication of 4 amperes DC is observed on the DC AMMETER in the Unit #1.
27. Rotate AC CONTROL Knob until pickup is detected by the CONTINUITY Lamp or TONE Generator. Read and record the value of current indicated by the AC AMMETER on Unit #1.

NOTE: While adjusting the AC CONTROL Knob, make necessary adjustments using AC ADJUST Control Knob to maintain 4 amperes DC on the DC AMMETER.

28. Return the AC CONTROL Knob to "0".
29. Return the AC ADJUST Knob to "0" and de-initiate the test set.

TESTING INSTANTANEOUS UNIT

30. Place INITIATE CONTROL in the MOM. Position.
31. Set AC AMMETER RANGE Switch on UNIT #1 to the 200A position.
32. Connect test leads of Unit #1 to terminals 3 and 5 of the relay.
33. Disconnect the test leads from Unit #2.
34. Block harmonic and differential units open.
35. Initiate unit by holding in INITIATE Pushbutton.
36. Rotate AC CONTROL Knob clockwise to increase current until pickup is detected by the CONTINUITY Lamp or TONE Generator.
37. Read value of current on AC AMMETER and release INITIATE Pushbutton.
38. Record value of current on AC AMMETER.
39. De-initiate test set and remove all blocking from the relay.

CURRENT PHASE BALANCE RELAYS
Westinghouse Type CM
General Electric Type IJC

GENERAL

The Current Phase Balance Relay operates to trip a circuit breaker when the phase currents in a circuit become unbalanced by some predetermined amount. This relay compares the three phase currents of a line.

GENERAL ELECTRIC TYPE IJC

The General Electric IJC relay is composed of three individual induction discs with two coils per disc. One coil produces a contact closing torque on the disc and is called an operating coil. The second coil produces a contact opening torque on the disc and is called a restraint coil. These two coils see currents from different phases of the circuit and the relay will operate when the phase currents become sufficiently unbalanced. The trip circuit contacts associated with all three induction discs are connected in parallel.

TYPES OF TESTS

Pickup
Timing
Slope
Target and Seal-In

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	Set to read test current in upper section of meter scale.
DC or AC VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
OUTPUT SELECT AC Switch	0-25A
AC AMMETER RANGE Switch	25A
AC ADJUST CONTROL Knob	"0"
AC INITIATE Switch	NORMAL
VOLTAGE SELECTOR Switch	AC; 150V
AUX ADJUST Control Knob	"0"
NORMAL/DROPOUT Switch	NORMAL
AUX INITIATE Switch	NORMAL

TESTING PICKUP

1. Connect one current operating coil of the relay to the 8.75A terminal and the COMMON ($\pm$). Observe polarity.
2. Initiate test set by depressing the INITIATE Switch.
3. Slowly increase current by rotating AC CONTROL Knob and VERNIER Control Knob clockwise until relay disc moves and contacts are closed. Then decrease current until disc remains stationary.
4. Record this value of current as the pickup value.
5. Repeat for operating coils of the other two relay current operating coils.
6. Return Control Knobs to the "0" position and de-initiate test set.

TESTING TIMING

1. Set AC AMMETER RANGE Switch so that the desired test current can be read in upper 1/3 of the meter scale.
2. Set INITIATE CONTROL to MOM. and CURRENT MODE Switch from CONTINUOUS to MEMORY.
3. Set test current by "jogging" the INITIATE Switch and rotating the AC CONTROL Knob to increase the output until the ammeter registers the desired test current.

4. Set INITIATE CONTROL to the MAINT. position.
5. Using a pair of light leads, connect the relay trip circuit contact terminals to the STOP/MONITOR binding posts on Unit #1.
6. Reset TIMER by depressing the RESET button.
7. Initiate the test set by depressing the INITIATE Switch. The TIMER will initiate and when the relay contacts close, the TIMER will stop and de-energize the test set.
8. Read and record time indicated on the TIMER.
9. Repeat Steps 1 through 8 for operating coils of the other two relay coils.

TESTING SLOPE

1. Connect restraint coil to the 0-25A terminals, observing polarity.
2. Select the proper ammeter ranges for both Unit #1 and #2 AC Ammeters.
3. Set INITIATE CONTROL to MAINT.
4. Initiate the test set by pressing the INITIATE Switch.
5. Rotate AC ADJUST Control Knob clockwise to energize the restraint coil of relay unit under test.
6. Rotate AC CONTROL Knob clockwise to energize the operating coil of relay unit under test.
7. Regulate the two currents until the disc of the relay under test is stopped with that unit's trip circuit contacts. (About halfway between full open position and trip position.)
8. Record both values of current and calculate slope.
9. Repeat Steps 1 through 8 for the other relay units.

WESTINGHOUSE TYPE CM RELAY

- The Westinghouse Type CM relay has two individual induction discs. Each disc has two current coils. One coil produces torque to move the disc to the left and the other coil produces torque to move the disc to the right. As long as the currents energizing the two coils are equal, the torques cancel and the disc remains stationary. In connecting the relay in the circuit, the coil producing rotation to the right on one disc is in "A" Phase, while the coil producing rotation to the left on the same disc is in "B" Phase. Each unit of the relay has a moving contact attached to the disc shaft and two stationary contacts, one on the right and one on the left. When the relay is energized with balanced 3-phase currents, the moving contacts of both relay units should be midway between the left and right stationary contacts. An unbalance of the phase currents will cause either or both of the discs to rotate with subsequent closing of the relay trip circuit contacts. The relay trip circuit contacts are connected in parallel.

TYPES OF TESTS

Electrical Balance
Minimum Trip Setting
Operating Curve
Time Curve

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
AC AMMETER RANGE Switch	So that the desired test current can be read in the upper 1/3 of the scale.
DC/OFF/VERNIER Switch	VERNIER
DC or AC VERNIER Control Knob	"0"

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
OUTPUT SELECT Switch	0-25A

AC AMMETER RANGE SELECTOR Switch	25A
AC ADJUST Control Knob	"0"
AC INITIATE Switch	NORMAL

TESTING ELECTRICAL BALANCE

1. Connect the 17.5A and COMMON ($\pm$) binding posts of Unit #1 to the relay's front current operating coil of one induction disc unit.
2. Connect the 0-25A and COMMON ($\pm$) binding posts of Unit #2 to the rear operating coil of the same induction disc unit.
3. Initiate unit by pressing the INITIATE Switch.
4. Rotate AC ADJUST Control Knob clockwise to obtain a reading of 6 amperes on the AC Ammeter, of Unit #2.
5. Rotate AC CONTROL Knob clockwise to obtain a reading of 6 amperes on the Ammeter of Unit #1.
6. The moving contact of the induction disc unit under test should be in a balanced position as described in relay the manufacturer's literature.
7. Return AC CONTROL Knob on Unit #1 and AC ADJUST Control Knob on Unit #2 to "0" and de-initiate the test set.

MINIMUM TRIP SETTING

1. Repeat Steps 1 through 3 under TESTING ELECTRICAL BALANCE.
2. Connect light leads from STOP/MONITOR binding posts on the test set to the trip circuit contacts of the relay.
3. Rotate AC CONTROL Knob clockwise to obtain a reading of 1 ampere on the AC Ammeter, of Unit #1.
4. Adjust the left stationary contact until it just makes with the moving contact as indicated by glowing of the CONTINUITY light or the sounding of the TONE generator.
5. Return AC CONTROL Knob to "0".
6. Rotate AC ADJUST Control Knob clockwise to obtain a reading of 1 ampere on the AC Ammeter of Unit #2.

7. Adjust right stationary contact until it just makes with moving contact, as indicated by glowing of CONTINUITY light or the sounding of the TONE generator.
8. Return AC ADJUST Control Knob to "0".

OPERATING CURVE

1. Repeat Steps 1 through 4 under TESTING ELECTRICAL BALANCE.
2. Connect light leads from STOP/MONITOR binding posts on the test set to the trip circuit contacts of the relay.
3. Rotate the AC CONTROL Knob clockwise until the moving contact and the right stationary contact make, as indicated by flickering of the CONTINUITY light. Record readings of both ammeters.
4. Slowly decrease current output of AC ADJUST Control knob by rotating it counterclockwise until the moving contact and left hand stationary contact just makes, as indicated by flickering of CONTINUITY light. Record readings of both ammeters.

TIME CURVE

1. Repeat Steps 1 through 3 under TESTING ELECTRICAL BALANCE. Set INITIATE CONTROL to MOM. position.
2. Connect a pair of light leads from STOP/MONITOR binding posts of the test set to trip circuit contact terminals of the relay.
3. "Jog" INITIATE Switch and rotate AC CONTROL Knob to obtain a reading of 10 amperes on the AC Ammeter.
4. Manually set moving contact to "Balance" position.
5. Set INITIATE CONTROL to MAINT. and the TIMER CONTROL to the INITIATE position.
6. Reset TIMER by pressing the RESET button.
7. Initiate the test set by pressing the INITIATE Switch. The unit will energize and the TIMER will initiate and when the relay contacts close, the TIMER will stop and the test set will de-energize.
8. Read and record time as indicated on the TIMER.
9. Return AC CONTROL Knob to "0". Set INITIATE CONTROL to the MOM. position.

10. "Jog" INITIATE Switch and rotate AC ADJUST Control Knob to obtain a reading of 10 amperes on AC Ammeter of Unit #2.

11. Manually set moving contact to "Balance" position.

12. Repeat steps 5 through 8 above.

Repeat all four tests, i.e. Electrical Balance, Minimum Trip Setting, Operating Curve and Time Curve for the other induction disc unit.

HIGH IMPEDANCE BUS DIFFERENTIAL RELAY Westinghouse Type KAB

GENERAL

The type KAB relay is connected so that under normal operating conditions, the voltage at the relay terminals is approximately zero. For an external fault, assuming that neither the source or feeder C.T.'s saturate, the voltage at the relay terminals remains zero.

In the case of an internal fault, the C.T.'s have, in effect, open-circuited primaries. The source C.T.'s will produce high voltages to drive the fault current through the feeder C.T.'s secondaries. This high voltage will appear at the relay terminals and cause the relay to operate.

The overcurrent unit will operate on current flow during severe internal faults when the varistor conducts current to limit the secondary voltage.

TYPES OF TESTS

Pickup Overvoltage
Timing Overvoltage
Pickup Overcurrent
Target and Seal-In

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

SET-UP OF CONTROLS IN UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	200A
DC or AC VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
OUTPUT SELECT Switch	0-600V AC
AC VOLTMETER RANGE Switch	200V
AC ADJUST CONTROL Knob	"0"
AC INITIATE Switch	NORMAL
AUX ADJUST Control Knob	"0"
AUX INITIATE Switch	NORMAL
NORMAL/DROPOUT Switch	NORMAL

TESTING FOR PICKUP

1. Connect the relay potential operating coil to the Red and Black binding posts of Unit #2 at the AC/DC OUTPUT binding posts.
2. Connect light leads from binding posts marked STOP/MONITOR to the trip circuit contact terminals of the relay induction unit.
3. Initiate unit by pressing the INITIATE Switch.
4. Rotate the AUX ADJUST Control Knob clockwise to increase output until CONTINUITY light flickers or the TONE generator sounds.
5. Record this value of voltage as pickup of the relay.

TESTING TIMING

6. Initiate the V. RELAY SECTION, the NORMAL light should be illuminated, set the NORMAL relay voltage by rotating AC ADJUST Control Knob clockwise, the normal voltage is displayed in the AC VOLTMETER.
7. Switch the TIMER CONTROL to V.RLY/D.O. and set the V. RLY Test Switch to the FAULT position.
8. Set the fault voltage by rotating the AUX ADJUST Control Knob clockwise, the fault voltage is displayed in the AUX AC VOLTMETER. NOTE: Set the fault voltage approximately 1 to 2 volts higher than the desired test voltage.
9. Switch the V. RELAY Test Switch to the TEST position. The FAULT Voltage is now impressed on the relay operating coil and the TIMER will initiate.

10. When the relay trip circuit contacts make, the TIMER will stop to indicate the elapsed time of the test.

TESTING FOR PICKUP OF OVERCURRENT UNIT

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MOM.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
AC AMMETER RANGE Switch	20A
CURRENT MEMORY/CONTINUOUS Switch	MEMORY
DC/OFF/VERNIER Switch	VERNIER
DC or AC VERNIER Control Knob	"0"

1. Connect the relay overcurrent unit operating coil to the 8.75A and the COMMON ($\pm$) of Unit #1. For the HI setting use the 35A output binding post.
2. Connect the overcurrent unit trip circuit contacts to the STOP/MONITOR binding posts of the test set.
3. Initiate unit by holding in INITIATE button.
4. Slowly rotate the AC CONTROL knob clockwise to increase current until the CONTINUITY light glows or TONE signal sounds. Make sure this is minimum setting on the AC CONTROL where the overcurrent unit of the relay will consistently pickup as the INITIATE button is alternately initiated and de-initiated.
5. Record this value of current using the CURRENT MEMORY Ammeter.
6. De-initiate test set by releasing the initiate button.

TARGET AND SEAL-IN

The DC TARGET AND SEAL-IN unit can be tested following the procedure given in the test procedures for testing an overcurrent relay.

DIFFERENTIAL VOLTAGE RELAY

General Electric Type PVD

GENERAL

This relay is a high speed bus differential relay which contains two operating units connected in parallel. One of the units (known as 87L) is an instantaneous voltage unit having a high impedance operating coil connected across the DC terminals of a full wave rectifier. The rectifier is connected in series with a reactor-capacitor combination tuned for resonance at rated frequency. The other unit (known as 87H) is an instantaneous overcurrent unit with a low impedance operating coil which is connected in series with Thyrite resistor stacks. Both of these units are connected in parallel with the secondaries of all current transformers on all the circuits associated with the bus to be protected. The current transformers on all the circuits associated with the bus to be protected. The current transformers should all have the same ratios.

The purpose of the 87L unit is to allow designation of the minimum internal fault that will operate the relay to trip all circuit breakers associated with the protected bus. The purpose of the 87H unit is to provide instantaneous operation for extremely severe internal faults.

Testing General Electric Type PVD11C Relays

NOTE: Set both the 87L and 87H units in low ranges.

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TESTING

TESTS

1. PICKUP OF 87L ELEMENT
2. PICKUP OF 87H ELEMENT
3. TESTING LEAKAGE OF THYRITE

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MOM.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER/VOLTMETER RANGE Switch	200V

DC or AC VERNIER Control knob	0
DC AMMETER RANGE Switch	5A

TESTING FOR PICKUP OF 87L ELEMENT

1. Connect the relay 87L unit operating coil to the 0-160V and COMMON ($\pm$) binding posts.
2. Connect light leads from binding posts marked STOP/MONITOR to the trip circuit contact terminals of the relay induction unit.
3. Jumper the relay terminals so that the relay 87H operating coil circuit is connected in parallel with the 87L operating coil circuit.
4. Initiate unit by pressing and holding in the INITIATE Switch.
5. Rapidly rotate the AC CONTROL Knob clockwise until the meter indicates an applied voltage approximately 25 volts higher than setting of the relay 87L unit. The CONTINUITY light should glow. Release the INITIATE Switch.
6. "Jog" the INITIATE Switch while reducing the applied voltage by rotating the AC CONTROL Knob counterclockwise. Determine minimum voltage which closed the relay 87L trip circuit contacts as indicated by the CONTINUITY light.
7. Record this value of voltage as pickup of 87L element.

TESTING PICKUP OF 87L ELEMENT

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
AC AMMETER RANGE Switch	So that the desired test current can be read in the UPPER 1/3 of the scale
DC or VERNIER Switch	VERNIER
DC or VERNIER Control Knob	"0"

DC AMMETER RANGE Switch

5A

1. Connect the appropriate current output binding posts to the relay terminals so that the operating coil of the relay 87H unit may be energized with the Thyrite resistor discs out of the circuit.
2. Connect the STOP/MONITOR binding posts of the test set to the trip circuit contacts terminals of the relay.
3. Initiate unit by pressing INITIATE Switch.
4. Slowly increase current to the relay operating coil by rotating AC CONTROL and AC VERNIER clockwise until CONTINUITY light glows or TONE generator sounds.
5. Record this value of current as "pickup" of the 87H unit.

TESTING THYRITE LEAKAGE

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
HORN/MONITOR Switch	Either Position
INITIATE CONTROL	MAINT.
AC CURRENT Control Knob	"0"
AC AMMETER RANGE Switch	200A
DC or VERNIER Control Switch	DC
DC AMMETER/VOLTMETER RANGE Selector	150V

1. Connect the Red (+) and Black (-) DC Output binding posts of the test set to the relay terminals so that the Thyrite resistor discs may be independently energized. A 0-15 milliamperes DC meter should be connected in series with this circuit.
2. Initiate unit by pressing INITIATE Switch.
3. Rotate DC VERNIER knob clockwise to increase output to 120 volts DC.
4. Read current on milliammeter. Compare with relay manufacturer's specifications.

TESTING INSTANTANEOUS VOLTAGE RELAYS

Westinghouse Type SV, SV-1

General Electric Type PJV

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TEST

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either position
AC CONTROL Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER/VOLTMETER RANGE Selector	200V
DC or AC VERNIER Control Knob	"0"
DC AMMETER/VOLTMETER RANGE Selector	5A

TESTING FOR PICKUP

1. Connect the relay operating coil to the 0-160V and COMMON ($\pm$) binding posts.
2. Connect light leads from binding posts marked STOP/MONITOR to the trip circuit contact terminals of the relay induction unit.
3. Initiate unit by pressing the INITIATE Switch.
4. Rotate the AC CONTROL Knob clockwise to increase output until CONTINUITY light flickers or the TONE generator sounds.
5. Record this value of voltage as pickup of the relay.
6. Continue to rotate AC CONTROL Knob clockwise until relay normal voltage (on relay nameplate) is read on voltmeter.
7. Rotate AC CONTROL Knob counterclockwise to decrease voltage until the CONTINUITY light just glows.

8. Read and record this value of voltage as dropout. ✎
9. De-initiate test set and return all control knobs to "0".

PILOT WIRE RELAY
Westinghouse Type HCB

GENERAL

The HCB relay is a three-phase high speed pilot wire relay designed for simultaneous tripping at the terminals of a power line. The power line three-phase currents energize the relay operating circuits through current transformers and are converted by a combination positive and zero sequence filters into a single phase output voltage. The single-phase output voltages from the HCB relays which are located at each power line terminal, normally have polarity to cause a circulating current through the pilot wire. When a fault occurs between the terminals of the power line, polarity of the single-phase output voltages to oppose each other in the pilot wire. Therefore, the output voltage of each relay is bypassed through the relay operating coil causing relay trip circuit contact closure.

**ALWAYS CONSULT THE MANUFACTURER'S INSTRUCTION LEAFLET
FOR PROPER CONNECTIONS AND INFORMATION ON RELAY
CHARACTERISTICS BEFORE TESTING.**

TYPE OF TESTS

Phase to Neutral Pickup
Phase to Phase Pickup
Target and Seal-In Pickup

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either Position
AC CONTROL Knob	"0"
DC/VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	As desired
DC or VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

TESTING PHASE TO NEUTRAL PICKUP

1. Connect 8.75A and COMMON ($\pm$) terminals to the relay terminals designated for testing "Phase A" to Neutral.
2. Connect binding posts marked STOP/MONITOR to relay trip circuit contacts.
3. Initiate unit by pressing INITIATE Switch.
4. Slowly increase current by rotating AC CONTROL Knob and the VERNIER Control Knob clockwise until CONTINUITY light glows or TONE breaks.
5. Record this value of current as pickup.
6. Repeat for "PHASE B" to Neutral and "PHASE C" to Neutral.

TESTING PHASE TO PHASE PICKUP

Repeat Steps 1 through 6 above except that the current output is connected to the relay terminals to pass current from Phase "B" to Phase "C" in series. Repeat for Phase "C" to "A" and Phase "A" to "B".

TESTING TARGET AND SEAL-IN PICKUP

Block relay trip circuit contacts closed and follow test procedures for testing DC Target and Seal-In.

TESTING GROUND DIRECTIONAL OVERCURRENT RELAYS
Westinghouse Type IRD, KRD and
General Electric Type JBCG

PLEASE REFER TO THE MANUFACTURER'S INSTRUCTION BULLETIN
BEFORE PROCEEDING WITH TEST.

TYPES OF TESTS

1. Pickup - voltage polarized directional element
2. Pickup - current polarized directional element
3. Pickup - overcurrent element
4. Timing - overcurrent element
5. Pickup - instantaneous element
6. DC TARGET
7. DC Auxiliary Switch (IRD)

TESTING PICKUP - Voltage Polarized Directional Element

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TEST

SET-UP OF CONTROLS ON UNIT #1

POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either Position
AC CONTROL Knob	"0"
DC/OFF/VERNIER Switch	VERNIER
AC AMMETER/VOLTMETER RANGE Switch	2A
DC or AC VERNIER Control Knob	"0"
DC AMMETER/VOLTMETER RANGE Switch	5A

SET-UP OF CONTROLS ON UNIT #2

<u>CONTROL</u>	<u>POSITION</u>
0-25A/0-300V/0-600V Output Select	0-25A
AC AMMETER RANGE Switch	2A

0-25A or 0-300V AC Adjust Knob	"0"
AUX VOLTMETER RANGE Switch	2V
NORMAL/EXT.PWR. Switch	Normal
AUXILIARY ADJUST Control Knob	"0"
NORM./BYPASS Switch	NORM.
AUX. OUTPUT Voltage Selector Switch	D.E.T.
NORM./DROPOUT	NORM.

1. Connect the polarity terminal ($\pm$) of the relay's current directional unit operating coil to the Black polarity binding post ($\pm$) of the voltage AC/DC OUTPUT section. The other side of the relay's current operating coil terminal should be connected to the 0-25A Blue binding post.
2. Connect the polarity ($\pm$) terminal of the relay voltage polarizing coil to the Red binding post of the AC/DC OUTPUT section. Place a jumper from the non-polarity terminal of voltage polarizing coil to polarity ($\pm$) terminal of the current polarizing coil.
3. Set the D.E.T Selector switch to the desired position.

NOTE: Positions 1, 2, and 3 are factory wired to produce values given below:

<u>POSITION</u>	<u>VOLTS</u>	<u>AMPERES</u>
1	1	2
	2	4
2	1	4
	2	8
3	1	8

4. The instantaneous element contacts on the IRD, the overcurrent element (I) contacts on the KRD relay and the (IOC) contacts on the JBCG relays should be blocked closed.
5. Connect a set of leads from the binding posts labeled STOP/MONITOR on the test set to the relay terminals associated with the normally open contacts of the directional element.
6. Initiate test set by depressing INITIATE Switch.

7. Rotate AC ADJUST Control Knob clockwise to increase output until the relay directional unit contacts close. Read and record the values of voltage and current on the respective meters.
8. Reverse test leads from test set to potential coil of relay, simulating a 180 degree phase shift. The relay's directional unit contacts should resist closure.
9. Rotate AC ADJUST Knob to "0" and de-initiate test set.
10. Remove blocking from relay.

TESTING PICKUP - Current Polarized Directional Element

1. Connect a set of test leads from the 8.75A and COMMON ($\pm$) binding posts of Unit #1 to the directional unit operating and polarizing current coils so the current will pass through the two coils in series.

Note: This can be achieved by connecting the COMMON ($\pm$) binding post of Unit #1 the polarity ($\pm$) terminal of the directional unit current operating coil. Connect a jumper from the other side of coil to the polarity ($\pm$) terminal of the directional unit current polarizing coil. The non-polarity terminal of the polarizing coil is then connected to the 8.75A binding post of Unit #1.

2. The instantaneous element contacts on the IRD and JBCG relays and the overcurrent element (I) contacts on the KRD relay should be blocked close.
3. Connect a set of leads from the binding posts labeled STOP/MONITOR on the test set to the relay terminals associated with the normally open contacts of the directional element.
4. Initiate test set by depressing INITIATE Switch.
5. Rotate AC CONTROL and VERNIER Control Knobs clockwise to increase current output until the relay directional element contacts close. Read and record value of current on the AC Ammeter.
6. Rotate AC CONTROL and VERNIER Controls knobs to "0" and de-initiate test set.
7. Remove blocking from relay.

TESTING DC AUXILIARY Switch - Minimum Pickup (IRD only) -

SET-UP OF CONTROLS ON UNIT #1

POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either Position
AC CONTROL Knob	"0"
DC or VERNIER Switch	DC
AC AMMETER/VOLTMETER RANGE Switch	2A
DC or AC VERNIER Control Knob	"0"
DC AMMETER/VOLTMETER RANGE Switch	150V

1. Block one of the directional elements normally open contacts closed.
2. Connect a set of leads from the Red (+) and Black (-) binding posts of the DC OUTPUT Section to the DC auxiliary switch coil terminals of the relay.
3. Initiate the test set by depressing the INITIATE Switch.
4. Rotate the DC VERNIER Control Knob clockwise to increase DC Voltage output until the auxiliary switch on the relay operates as indicated by a "click". Read and record the voltage indicated on voltmeter.
5. Rotate the DC VERNIER Control Knob to "0" and de-initiate the test set.
6. Remove blocking from relay.

TESTING OVERCURRENT ELEMENT - Pickup and Time Current Characteristics; INSTANTANEOUS ELEMENT - Pickup; and DC TARGET and SEAL-IN

1. Block one of the directional elements normally open contacts closed. (The IRD relay's auxiliary switch contacts must also be blocked in a closed position).
2. Follow the procedure for testing "Induction Disc Overcurrent Relay Type IAC or CO".
3. Remove all blocking from relay when testing is completed.

FAULT DETECTOR RELAY
General Electric Type CHC

GENERAL

The CHC11A relay is a three-phase, nondirectional overcurrent relay, with ground fault detection.

The CHC11B is similar to the CHC11A except it has a dual rated auxiliary telephone relay.

The CHC12A is a 3Ø, high speed, nondirectional overcurrent relay. The relay consists of a (PFD) induction CUP unit.

TYPE OF TESTS

Pickup - (PFD) Cup Unit

Pickup - (GFD) Hinged Armature Unit (11 A & B only)

Target and Seal-In

ALWAYS REFER TO THE MANUFACTURER'S LITERATURE BEFORE TEST

SET-UP OF CONTROLS ON UNIT #1

<u>CONTROL</u>	<u>POSITION</u>
POWER ON/OFF Switch	ON
INITIATE CONTROL	MAINT.
HORN/MONITOR Switch	Either Position
AC CONTROL Knob	"0"
DC or VERNIER Switch	VERNIER
AC AMMETER RANGE Switch	As Desired
DC or DC VERNIER Control Knob	"0"
DC AMMETER RANGE Switch	5A

TESTINGS PICKUP - (PFD) CUP UNIT

To test pickup of the (PFD) Cup Unit on the CHC11, it is necessary to place two phases of current in series by placing a jumper from relay terminals 4 to 6. The CHC12 requires a jumper from relay terminals 3 to 6.

1. Connect the 8.75A binding post to relay terminal 3 and the COMMON ($\pm$) binding post to relay terminal 5.
2. Perform the same test procedure as outlined under INDUCTION DISC OVERCURRENT RELAY, Pickup Test.

PICKUP - (GFD) HINGED ARMATURE UNIT


1. Perform the same test procedure as outlined under INDUCTION DISC OVERCURRENT RELAY, *Testing Instantaneous Pickup*.

Note: The pickup point for the GFD unit varies from only 0.5 to 8 amperes, therefore use the 8.75A output instead of the 140A output as recommended in the *Testing Instantaneous Pickup* test procedures.

TARGET AND SEAL-IN

1. Use the test procedure for testing DC Target and Seal-In relays.

SCHEMATIC AND PARTS LIST




AVO MULTI-2742		12141 333-2901	
COMPOSITION		4273 BROOKLYN AVE DALLAS TEXAS 75223	
TITLE			
SR-5C	SR-5C	SR-5C	SR-5C
SR-80-115-1	SR-80-115-1	SR-80-115-1	SR-80-115-1
261220	261220	261220	261220
2	2	2	2


REF. DES.	PART NO.	DESCRIPTION	QTY.
T4	12744	ASY CABLE CT SR80	1
	12688	ASY CABLE P4H SR80	1
	12687	KNOB RD BAR TYPE FEH 1/4-20	1
	12666	KNOB BK BAR TYPE FEH 1/4-20	1
	12663	ASY CABLE OC MTR INPUT SR80	1
	12662	ASY CABLE VOLT SIGNAL SR80	1
	12627	CABLE START/STOP SR80	1
	12626	CABLE MTR 40/C SR80	1
	12617	CABLE TCH/RLV SR80 UNIT 1	1
	12616	CABLE TCH/REAR PNL SR80 UNIT 1	1
R4	12556	RES 0.05 15W 1% CHAS MTR	1
KA, 3, 10, 11	12186	RELAY 1PST 18A/250V 24VDC	4
T6	12103	TRANSF 115/230 5 & 15 VDC	1
C2	12102	CAP MFD 5000 30V ALUM CAN	1
C1	12101	CAP MFD 1000 450V ALUM CAN	1
T8, 7	12090	TRANSF 115/230 5 & 15 VDC	2
R1	12089	RES K 6.0 5% 25W HW FIXED	1
	12077	ASY PCB TCH SR80	1
T3	12064	TRANSF VERN DC SR80	1
T5	12053	TRANSF OUTPUT SR80 UNIT 1	1
S1	12055	SW 2PST 20A ON-ON TCL	1
X4-9	12044	RELAY 1PST 15A 120VAC 24VDC	2
X5-8	12043	RELAY 1PST 15A NO 24VDC	4
X1	12042	RELAY 1PST 30A NO 250VAC 24VDC	1
T2	12041	KNOB 1.25 MIL GRV .25 HOLE	1
T1	12040	KNOB 0.7 MIL GRV .25 HOLE	1
F1-8	12036	FUSE HOLDER MTR-481 BODY BUSB	9
92	10605	SW 2PST ROTARY PNL MT 800EG	1
MOV1-4	X3173	VARIATOR V130LA10A	4
R3	R1, 5K0205	RES K 1.5 5% 2W	1
J5	JHL1148	CONN PHONE JACK 3 COND	1

REF. DES.	PART NO.	DESCRIPTION	QTY.
	11321	ASY PCB TIMER DISPLAY	2
	12078	ASY PCB OC MEASUREMENT	1
F9	982	FUSE 0.5A 250V MDA	1
F1	903	FUSE 15A 250V MDA	1
F3, 6, 9	952	FUSE 3A 250V MDA	3
F2	951	FUSE 3A 250V MDA	1
X12	9208	RELAY AROHMT 9P2 24VDC EP	1
F7, 8	9043	FUSE 20A 250V MDA	2
FL1	8008	FILTER PFI 115-230V3 AMP OCR	1
T2	610	TRANSF VAR 120V 10A	1
T1	608	TRANSF VAR 120V 2.5A	1
D2	5232	DIODE BRIDGE 10A 600V CHAS MT	1
TR1	4922	TRIAC 25A 800V S876A	1
D1	4708	DIODE BRIDGE 25A 800V CHAS MT	1
F4	4139	FUSE 1.0A 250V MDA	1
FAN	3175	FAN 120CFM 115V 50/60 HZ	1
R2	2183	RES 0.100 5% 12W	1

MULTI-AMP		1144 235-2001
COMPONENT		1144 235-2001
TITLE		1144 235-2001
SCN - SR-80, 115V, UNIT 1	3 of 3	
SR-80-115-1	261220	



MULTI-AMP		4271 802TH WAY DALLAS TEXAS 75227	
COMBINATION		DATE 6/80	
NAME	A O C	1ST 3RD	DATE
TITLE	SCH	SR-90	1157 UNIT 2
PRINT NO	DATE	NO	SHEET
SR-90-115-2	261230		1 of 3
			PAGE




REF.	DES.	PART NO.	DESCRIPTION	QTY.
		12293	ASY PCB MEASUREMENT SRBO UNIT E	1
		86	SH 220T 1000LE 15A	1
		F6.7	FUSE 15A 250V HDA	2
		F1	FUSE 6A 250V HDA	1
		F4, 5, 8	FUSE 5A 250V HDA	3
		F2	FUSE 5A 250V HDA	3
		F1	FUSE 1.5A 250V HDA	1
		X1	RELAY ARMOAT SPZ 24VDC EP	1
		9208	RELAY ARMOAT 115-230V3 AMP OCR	1
		FL1	FILTER PEI 115-230V3	1
		8008	TRANSF VAR 120V 5A	1
		T2	TRANSF VAR 120V 2.5A	1
		T1	TRANSF VAR 120V 2.5A	1
		9232	DIODE BR10DE 10A 600V CHAS MT	1
		D2	DIODE BR10DE 25A 200V CHAS MT	1
		D1	DIODE BR10DE 25A 200V CHAS MT	1
		4708		1

MULTI-DISC		78101 333-3201	
COOPERATION			
4211 BACILE MAE DALLAS TEXAS 75227			
TITLE		UNIT	
SCH. SR-97.	1157	LIT 2	303
PLANT NO			
SR-90-1157	251230		2

REV.	DATE	BY	CHKD.
1	7/1/58	J. S. W.	
2	7/1/58	J. S. W.	


SH. 2, 2.7
SH. 3, 4.8
SH. 4, 10
SH. 5, 15
SH. 6, 20
SH. 7, 25
SH. 8, 30
SH. 9, 35
SH. 10, 40
SH. 11, 45
SH. 12, 50
SH. 13, 55
SH. 14, 60
SH. 15, 65
SH. 16, 70
SH. 17, 75
SH. 18, 80
SH. 19, 85
SH. 20, 90
SH. 21, 95
SH. 22, 100
SH. 23, 105
SH. 24, 110
SH. 25, 115
SH. 26, 120
SH. 27, 125
SH. 28, 130
SH. 29, 135
SH. 30, 140
SH. 31, 145
SH. 32, 150
SH. 33, 155
SH. 34, 160
SH. 35, 165
SH. 36, 170
SH. 37, 175
SH. 38, 180
SH. 39, 185
SH. 40, 190
SH. 41, 195
SH. 42, 200
SH. 43, 205
SH. 44, 210
SH. 45, 215
SH. 46, 220
SH. 47, 225
SH. 48, 230
SH. 49, 235
SH. 50, 240
SH. 51, 245
SH. 52, 250
SH. 53, 255
SH. 54, 260
SH. 55, 265
SH. 56, 270
SH. 57, 275
SH. 58, 280
SH. 59, 285
SH. 60, 290
SH. 61, 295
SH. 62, 300
SH. 63, 305
SH. 64, 310
SH. 65, 315
SH. 66, 320
SH. 67, 325
SH. 68, 330
SH. 69, 335
SH. 70, 340
SH. 71, 345
SH. 72, 350
SH. 73, 355
SH. 74, 360
SH. 75, 365
SH. 76, 370
SH. 77, 375
SH. 78, 380
SH. 79, 385
SH. 80, 390
SH. 81, 395
SH. 82, 400
SH. 83, 405
SH. 84, 410
SH. 85, 415
SH. 86, 420
SH. 87, 425
SH. 88, 430
SH. 89, 435
SH. 90, 440
SH. 91, 445
SH. 92, 450
SH. 93, 455
SH. 94, 460
SH. 95, 465
SH. 96, 470
SH. 97, 475
SH. 98, 480
SH. 99, 485
SH. 100, 490
SH. 101, 495
SH. 102, 500
SH. 103, 505
SH. 104, 510
SH. 105, 515
SH. 106, 520
SH. 107, 525
SH. 108, 530
SH. 109, 535
SH. 110, 540
SH. 111, 545
SH. 112, 550
SH. 113, 555
SH. 114, 560
SH. 115, 565
SH. 116, 570
SH. 117, 575
SH. 118, 580
SH. 119, 585
SH. 120, 590
SH. 121, 595
SH. 122, 600
SH. 123, 605
SH. 124, 610
SH. 125, 615
SH. 126, 620
SH. 127, 625
SH. 128, 630
SH. 129, 635
SH. 130, 640
SH. 131, 645
SH. 132, 650
SH. 133, 655
SH. 134, 660
SH. 135, 665
SH. 136, 670
SH. 137, 675
SH. 138, 680
SH. 139, 685
SH. 140, 690
SH. 141, 695
SH. 142, 700
SH. 143, 705
SH. 144, 710
SH. 145, 715
SH. 146, 720
SH. 147, 725
SH. 148, 730
SH. 149, 735
SH. 150, 740
SH. 151, 745
SH. 152, 750
SH. 153, 755
SH. 154, 760
SH. 155, 765
SH. 156, 770
SH. 157, 775
SH. 158, 780
SH. 159, 785
SH. 160, 790
SH. 161, 795
SH. 162, 800
SH. 163, 805
SH. 164, 810
SH. 165, 815
SH. 166, 820
SH. 167, 825
SH. 168, 830
SH. 169, 835
SH. 170, 840
SH. 171, 845
SH. 172, 850
SH. 173, 855
SH. 174, 860
SH. 175, 865
SH. 176, 870
SH. 177, 875
SH. 178, 880
SH. 179, 885
SH. 180, 890
SH. 181, 895
SH. 182, 900
SH. 183, 905
SH. 184, 910
SH. 185, 915
SH. 186, 920
SH. 187, 925
SH. 188, 930
SH. 189, 935
SH. 190, 940
SH. 191, 945
SH. 192, 950
SH. 193, 955
SH. 194, 960
SH. 195, 965
SH. 196, 970
SH. 197, 975
SH. 198, 980
SH. 199, 985
SH. 200, 990
SH. 201, 995
SH. 202, 1000
SH. 203, 1005
SH. 204, 1010
SH. 205, 1015
SH. 206, 1020
SH. 207, 1025
SH. 208, 1030
SH. 209, 1035
SH. 210, 1040
SH. 211, 1045
SH. 212, 1050
SH. 213, 1055
SH. 214, 1060
SH. 215, 1065
SH. 216, 1070
SH. 217, 1075
SH. 218, 1080
SH. 219, 1085
SH. 220, 1090
SH. 221, 1095
SH. 222, 1100
SH. 223, 1105
SH. 224, 1110
SH. 225, 1115
SH. 226, 1120
SH. 227, 1125
SH. 228, 1130
SH. 229, 1135
SH. 230, 1140
SH. 231, 1145
SH. 232, 1150
SH. 233, 1155
SH. 234, 1160
SH. 235, 1165
SH. 236, 1170
SH. 237, 1175
SH. 238, 1180
SH. 239, 1185
SH. 240, 1190
SH. 241, 1195
SH. 242, 1200
SH. 243, 1205
SH. 244, 1210
SH. 245, 1215
SH. 246, 1220
SH. 247, 1225
SH. 248, 1230
SH. 249, 1235
SH. 250, 1240
SH. 251, 1245
SH. 252, 1250
SH. 253, 1255
SH. 254, 1260
SH. 255, 1265
SH. 256, 1270
SH. 257, 1275
SH. 258, 1280
SH. 259, 1285
SH. 260, 1290
SH. 261, 1295
SH. 262, 1300
SH. 263, 1305
SH. 264, 1310
SH. 265, 1315
SH. 266, 1320
SH. 267, 1325
SH. 268, 1330
SH. 269, 1335
SH. 270, 1340
SH. 271, 1345
SH. 272, 1350
SH. 273, 1355
SH. 274, 1360
SH. 275, 1365
SH. 276, 1370
SH. 277, 1375
SH. 278, 1380
SH. 279, 1385
SH. 280, 1390
SH. 281, 1395
SH. 282, 1400
SH. 283, 1405
SH. 284, 1410
SH. 285, 1415
SH. 286, 1420
SH. 287, 1425
SH. 288, 1430
SH. 289, 1435
SH. 290, 1440
SH. 291, 1445
SH. 292, 1450
SH. 293, 1455
SH. 294, 1460
SH. 295, 1465
SH. 296, 1470
SH. 297, 1475
SH. 298, 1480
SH. 299, 1485
SH. 300, 1490
SH. 301, 1495
SH. 302, 1500
SH. 303, 1505
SH. 304, 1510
SH. 305, 1515
SH. 306, 1520
SH. 307, 1525
SH. 308, 1530
SH. 309, 1535
SH. 310, 1540
SH. 311, 1545
SH. 312, 1550
SH. 313, 1555
SH. 314, 1560
SH. 315, 1565
SH. 316, 1570
SH. 317, 1575
SH. 318, 1580
SH. 319, 1585
SH. 320, 1590
SH. 321, 1595
SH. 322, 1600
SH. 323, 1605
SH. 324, 1610
SH. 325, 1615
SH. 326, 1620
SH. 327, 1625
SH. 328, 1630
SH. 329, 1635
SH. 330, 1640
SH. 331, 1645
SH. 332, 1650
SH. 333, 1655
SH. 334, 1660
SH. 335, 1665
SH. 336, 1670
SH. 337, 1675
SH. 338, 1680
SH. 339, 1685
SH. 340, 1690
SH. 341, 1695
SH. 342, 1700
SH. 343, 1705
SH. 344, 1710
SH. 345, 1715
SH. 346, 1720
SH. 347, 1725
SH. 348, 1730
SH. 349, 1735
SH. 350, 1740
SH. 351, 1745
SH. 352, 1750
SH. 353, 1755
SH. 354, 1760
SH. 355, 1765
SH. 356, 1770
SH. 357, 1775
SH. 358, 1780
SH. 359, 1785
SH. 360, 1790
SH. 361, 1795
SH. 362, 1800
SH. 363, 1805
SH. 364, 1810
SH. 365, 1815
SH. 366, 1820
SH. 367, 1825
SH. 368, 1830
SH. 369, 1835
SH. 370, 1840
SH. 371, 1845
SH. 372, 1850
SH. 373, 1855
SH. 374, 1860
SH. 375, 1865
SH. 376, 1870
SH. 377, 1875
SH. 378, 1880
SH. 379, 1885
SH. 380, 1890
SH. 381, 1895
SH. 382, 1900
SH. 383, 1905
SH. 384, 1910
SH. 385, 1915
SH. 386, 1920
SH. 387, 1925
SH. 388, 1930
SH. 389, 1935
SH. 390, 1940
SH. 391, 1945
SH. 392, 1950
SH. 393, 1955
SH. 394, 1960
SH. 395, 1965
SH. 396, 1970
SH. 397, 1975
SH. 398, 1980
SH. 399, 1985
SH. 400, 1990
SH. 401, 1995
SH. 402, 2000
SH. 403, 2005
SH. 404, 2010
SH. 405, 2015
SH. 406, 2020
SH. 407, 2025
SH. 408, 2030
SH. 409, 2035
SH. 410, 2040
SH. 411, 2045
SH. 412, 2050
SH. 413, 2055
SH. 414, 2060
SH. 415, 2065
SH. 416, 2070
SH. 417, 2075
SH. 418, 2080
SH. 419, 2085
SH. 420, 2090
SH. 421, 2095
SH. 422, 2100
SH. 423, 2105
SH. 424, 2110
SH. 425, 2115
SH. 426, 2120
SH. 427, 2125
SH. 428, 2130
SH. 429, 2135
SH. 430, 2140
SH. 431, 2145
SH. 432, 2150
SH. 433, 2155
SH. 434, 2160
SH. 435, 2165
SH. 436, 2170
SH. 437, 2175
SH. 438, 2180
SH. 439, 2185
SH. 440, 2190
SH. 441, 2195
SH. 442, 2200
SH. 443, 2205
SH. 444, 2210
SH. 445, 2215
SH. 446, 2220
SH. 447, 2225
SH. 448, 2230
SH. 449, 2235
SH. 450, 2240
SH. 451, 2245
SH. 452, 2250
SH. 453, 2255
SH. 454, 2260
SH. 455, 2265
SH. 456, 2270
SH. 457, 2275
SH. 458, 2280
SH. 459, 2285
SH. 460, 2290
SH. 461, 2295
SH. 462, 2300
SH. 463, 2305
SH. 464, 2310
SH. 465, 2315
SH. 466, 2320
SH. 467, 2325
SH. 468, 2330
SH. 469, 2335
SH. 470, 2340
SH. 471, 2345
SH. 472, 2350
SH. 473, 2355
SH. 474, 2360
SH. 475, 2365
SH. 476, 2370
SH. 477, 2375
SH. 478, 2380
SH. 479, 2385
SH. 480, 2390
SH. 481, 2395
SH. 482, 2400
SH. 483, 2405
SH. 484, 2410
SH. 485, 2415
SH. 486, 2420
SH. 487, 2425
SH. 488, 2430
SH. 489, 2435
SH. 490, 2440
SH. 491, 2445
SH. 492, 2450
SH. 493, 2455
SH. 494, 2460
SH. 495, 2465
SH. 496, 2470
SH. 497, 2475
SH. 498, 2480
SH. 499, 2485
SH. 500, 2490
SH. 501, 2495
SH. 502, 2500
SH. 503, 2505
SH. 504, 2510
SH. 505, 2515
SH. 506, 2520
SH. 507, 2525
SH. 508, 2530
SH. 509, 2535
SH. 510, 2540
SH. 511, 2545
SH. 512, 2550
SH. 513, 2555
SH. 514, 2560
SH. 515, 2565
SH. 516, 2570
SH. 517, 2575
SH. 518, 2580
SH. 519, 2585
SH. 520, 2590
SH. 521, 2595
SH. 522, 2600
SH. 523, 2605
SH. 524, 2610
SH. 525, 2615
SH. 526, 2620
SH. 527, 2625
SH. 528, 2630
SH. 529, 2635
SH. 530, 2640
SH. 531, 2645
SH. 532, 2650
SH. 533, 2655
SH. 534, 2660
SH. 535, 2665
SH. 536, 2670
SH. 537, 2675
SH. 538, 2680
SH. 539, 2685
SH. 540, 2690
SH. 541, 2695
SH. 542, 2700
SH. 543, 2705
SH. 544, 2710
SH. 545, 2715
SH. 546, 2720
SH. 547, 2725
SH. 548, 2730
SH. 549, 2735
SH. 550, 2740
SH. 551, 2745
SH. 552, 2750
SH. 553, 2755
SH. 554, 2760
SH. 555, 2765
SH. 556, 2770
SH. 557, 2775
SH. 558, 2780
SH. 559, 2785
SH. 560, 2790
SH. 561, 2795
SH. 562, 2800
SH. 563, 2805
SH. 564, 2810
SH. 565, 2815
SH. 566, 2820
SH. 567, 2825
SH. 568, 2830
SH. 569, 2835
SH. 570, 2840
SH. 571, 2845
SH. 572, 2850
SH. 573, 2855
SH. 574, 2860
SH. 575, 2865
SH. 576, 2870
SH. 577, 2875
SH. 578, 2880
SH. 579, 2885
SH. 580, 2890
SH. 581, 2895
SH. 582, 2900
SH. 583, 2905
SH. 584, 2910
SH. 585, 2915
SH. 586, 2920
SH. 587, 2925
SH. 588, 2930
SH. 589, 2935
SH. 590, 2940
SH. 591, 2945
SH. 592, 2950
SH. 593, 2955
SH. 594, 2960
SH. 595, 2965
SH. 596, 2970
SH. 597, 2975
SH. 598, 2980
SH. 599, 2985
SH. 600, 2990
SH. 601, 2995
SH. 602, 3000
SH. 603, 3005
SH. 604, 3010
SH. 605, 3015
SH. 606, 3020
SH. 607, 3025
SH. 608, 3030
SH. 609, 3035
SH. 610, 3040
SH. 611, 3045
SH. 612, 3050
SH. 613, 3055
SH. 614, 3060
SH. 615, 3065
SH. 616, 3070
SH. 617, 3075
SH. 618, 3080
SH. 619, 3085
SH. 620, 3090
SH. 621, 3095
SH. 622, 3100
SH. 623, 3105
SH. 624, 3110
SH. 625, 3115
SH. 626, 3120
SH. 627, 3125
SH. 628, 3130
SH. 629, 3135
SH. 630, 3140
SH. 631, 3145
SH. 632, 3150
SH. 633, 3155
SH. 634, 3160
SH. 635, 3165
SH. 636, 3170
SH. 637, 3175
SH. 638, 3180
SH. 639, 3185
SH. 640, 3190
SH. 641, 3195
SH. 642, 3200
SH. 643, 3205
SH. 644, 3210
SH. 645, 3215
SH. 646, 3220
SH. 647, 3225
SH. 648, 3230
SH. 649, 3235
SH. 650, 3240
SH. 651, 3245
SH. 652, 3250
SH. 653, 3255
SH. 654, 3260
SH. 655, 3265
SH. 656, 3270
SH. 657, 3275
SH. 658, 3280
SH. 659, 3285
SH. 660, 3290
SH. 661, 3295
SH. 662, 3300
SH. 663, 3305
SH. 664, 3310
SH. 665, 3315
SH. 666, 3320
SH. 667, 3325
SH. 668, 3330
SH. 669, 3335
SH. 670, 3340
SH. 671, 3345
SH. 672, 3350
SH. 673, 3355
SH. 674, 3360
SH. 675, 3365
SH. 676, 3370
SH. 677, 3375
SH. 678, 3380
SH. 679, 3385
SH. 680, 3390
SH. 681, 3395
SH. 682, 3400
SH. 683, 3405
SH. 684, 3410
SH. 685, 3415
SH. 686, 3420
SH. 687, 3425
SH. 688, 3430
SH. 689, 3435
SH. 690, 3440
SH. 691, 3445
SH. 692, 3450
SH. 693, 3455
SH. 694, 3460
SH. 695, 3465
SH. 696, 3470
SH. 697, 3475
SH. 698, 3480
SH. 699, 3485
SH. 700, 3490
SH. 701, 3495
SH. 702, 3500
SH. 703, 3505
SH. 704, 3510
SH. 705, 3515
SH. 706, 3520
SH. 707, 3525
SH. 708, 3530
SH. 709, 3535
SH. 710, 3540
SH. 711, 3545
SH. 712, 3550
SH. 713, 3555
SH. 714, 3560
SH. 715, 3565
SH. 716, 3570
SH. 717, 3575
SH. 718, 3580
SH. 719, 3585
SH. 720, 3590
SH. 721, 3595
SH. 722, 3600
SH. 723, 3605
SH. 724, 3610
SH. 725, 3615
SH. 726, 3620
SH. 727, 3625
SH. 728, 3630
SH. 729, 3635
SH. 730, 3640
SH. 731, 3645
SH. 732, 3650
SH. 733, 3655
SH. 734, 3660
SH. 735, 3665
SH. 736, 3670
SH. 737, 3675
SH. 738, 3680
SH. 739, 3685
SH. 740, 3690
SH. 741, 3695
SH. 742, 3700
SH. 743, 3705
SH. 744, 3710
SH. 745, 3715
SH. 746, 3720
SH. 747, 3725
SH. 748, 3730
SH. 749, 3735
SH. 750, 3740
SH. 751, 3745
SH. 752, 3750
SH. 753, 3755
SH. 754, 3760
SH. 755, 3765
SH. 756, 3770
SH. 757, 3775
SH. 758, 3780
SH. 759, 3785
SH. 760, 3790
SH. 761, 3795
SH. 762, 3800
SH. 763, 3805
SH. 764, 3810
SH. 765, 3815
SH. 766, 3820
SH. 767, 3825
SH. 768, 3830
SH. 769, 3835
SH. 770, 3840
SH. 771, 3845
SH. 772, 3850
SH. 773, 3855
SH. 774, 3860
SH. 775, 3865
SH. 776, 3870
SH. 777, 3875
SH. 778, 3880
SH. 779, 3885
SH. 780, 3890
SH. 781, 3895
SH. 782, 3900
SH. 783, 3905
SH. 784, 3910
SH. 785, 3915
SH. 786, 3920
SH. 787, 3925
SH. 788, 3930
SH. 789, 3935
SH. 790, 3940
SH. 791, 3945
SH. 792, 3950
SH. 793, 3955
SH. 794, 3960
SH. 795, 3965
SH. 796, 3970
SH. 797, 3975
SH. 798, 3980
SH. 799, 3985
SH. 800, 3990
SH. 801, 3995
SH. 802, 4000
SH. 803, 4005
SH. 804, 4010
SH. 805, 4015
SH. 806, 4020
SH. 807, 4025
SH. 808, 4030
SH. 809, 4035
SH. 810, 4040
SH. 811, 4045
SH. 812, 4050
SH. 813, 4055
SH. 814, 4060
SH. 815, 4065
SH. 816, 4070
SH. 817, 4075
SH. 818, 4080
SH. 819, 4085
SH. 820, 4090
SH. 821, 4095
SH. 822, 4100
SH. 823, 4105
SH. 824, 4110
SH. 825, 4115
SH. 826, 4120
SH. 827, 4125
SH. 828, 4130
SH. 829, 4135
SH. 830, 4140
SH. 831, 4145
SH. 832, 4150
SH. 833, 4155
SH. 834, 4160
SH. 835, 4165
SH. 836, 4170
SH. 837, 4175
SH. 838, 4180
SH. 839, 4185
SH. 840, 4190
SH. 841, 4195
SH. 842, 4200
SH. 843, 4205
SH. 844, 4210
SH. 845, 4215
SH. 846, 4220
SH. 847, 4225
SH. 848, 4230
SH. 849, 4235
SH. 850, 4240
SH. 851, 4245
SH. 852, 4250
SH. 853, 4255
SH. 854, 4260
SH. 855, 4265
SH. 856, 4270
SH. 857, 4275
SH. 858, 4280
SH. 859, 4285
SH. 860, 4290
SH. 861, 4295
SH. 862, 4300
SH. 863, 4305
SH. 864, 4310
SH. 865, 4315
SH. 866, 4320
SH. 867, 4325
SH. 868, 4330
SH. 869, 4335
SH. 870, 4340
SH. 871, 4345
SH. 872, 4350
SH. 873, 4355
SH. 874, 4360
SH. 875, 4365
SH. 876, 4370
SH. 877, 4375
SH. 878, 4380
SH. 879, 4385
SH. 880, 4390
SH. 881, 4395
SH. 882, 4400
SH. 883, 4405
SH. 884, 4410
SH. 885, 4415
SH. 886, 4420
SH. 887, 4425
SH. 888, 4430
SH. 889, 4435
SH. 890, 4440
SH. 891, 4445
SH. 892, 4450
SH. 893, 4455
SH. 894, 4460
SH. 895, 4465
SH. 896, 4470
SH. 897,




12686	ASY CABLE P.M. SR90	1
12687	KNOB NO BAR TYPE FEH 1/4-20	1
12688	KNOB BK BAR TYPE FEH 1/4-20	1
12689	ASY CABLE DC WTR INPUT SR90 U1	1
12692	ASY CABLE VOLT SIGNAL SR90-1	1
12693	CABLE R18 26/C	1
12697	CABLE STAYR/STOP SR90	1
12698	CABLE R18 40/C SR90	1
12617	CABLE TCH/VL SR90 UNIT 1	1
12616	CABLE TCH/NEAR PHL SR90 UNIT 1	1
12556	RES D .005 15K 1K CHAS RTG	1
12186	RELAY 1PBT 134B250V 24VDC	4
12103	TRANSF 115/220: 300V .7A CT	1
12102	CAP MFD 5000 30V ALUM CAN	1
12101	CAP MFD 1000 450V ALUM CAN	1
12090	TRANSF 115/220 5 C 15 VDC	2
12089	RES K 8.0 5K 25W WM FIXED	1
12077	ASY PCB TCH SR90	1
12064	TRANSF VERNI DC SR90	1
12063	TRANSF OUTPUT SR90 UNIT 1	1
12055	5W 2POT 20A ON-OH TOL	1
12044	RELAY 1PBT 15A 125VAC 24VDC	4
12043	RELAY 1PBT 15A NO 24VDC	1
12042	RELAY 1PBT 30A NO 250VAC 24VDC	1
12041	KNOB 1.25 MIL GRV .25 HOLE	2
12038	KNOB 0.7 MIL GRV .25 HOLE PRNT	2
11334	FUSE HOLDER HTB-481 BULO BUS5	1
11334	FAN 120CFM 230V 50/60 HZ	1
11006	5W 2POT ROTARY PHL MT 900EG	1
R3	RES K 1.5 5K 2W	1
REF. DES.	CONV PHONE JACK 3 CONO	1

REF. DES.	PART NO.	DESCRIPTION	QTY.
	12078	ASY PCB DC METER SR90	1
	11321	ASY PCB TIME DISPLAY	1
F1, 7, 8	984	FUSE 10A 250V MOA	3
F2, 6	983	FUSE 2.0A 250V MOA	2
F4, 5	982	FUSE 0.5A 250V MOL	2
F6	952	FUSE 5A 250V MOA	2
F2	950	FUSE 1.5A 250V MOA	1
T2	9484	TRANSF VAR 250V 2.5A SUP	1
X12	9208	RELAY ARQMAT SP2 250DC EP	1
MOV-4	8888	VARISTOR 320V	4
F1, 1	8009	FILTER PI 115-230V3 AMP OCR	1
T2	839	TRANSF VAR 250V 3.5A	1
D2	9232	DIODE BRIDGE 10A 600V CHAS MT	1
T81	4822	TRAC 25A 600V BR76A	1
O1	4706	DIODE BRIDGE 25A 200V CHAS MT	1
T1	3284	TRANSF VAR 250V 0.5A SUP	1
R2	2163	RES 0.100 5% 12W	1
T4	12744	ASY CABLE CT SP950	1
	12896	ASY CABLE SR90 U1	2

MULTI-AMP		(814) 388-3201
EXPEDITION		
4871 PROCTOR WAY DALLAS TEXAS 75227		
TITLE		QUEST
SCH.. SR-90, 230V, UNIT 1		3 OF 3
PART NO		
SR-90-230-1	Q-88 NO	277100



MULTI-AMP		(846) 338-3801	
COMPANY ID		4871 BRIDGE ST DALLAS, TEXAS 75237	
MODEL	A.O.C.	APPRO	S.M.N.
TITLE		DATE	
SCH. - SR-90 230V, UNIT 2		2-8-73	
PART NO.	DWG NO.	REV	
SR-90-230-2	27711D	2	



277110

REF. DES.	PART NO.	DESCRIPTION	QTY.
	12665	CABLE REAR PNL CONT SR80-2	1
	12664	ASY CABLE AC MTR INPUT SR80 U2	1
	12667	KNOB RD BAR TYPE FEH 1/4-20	1
	12635	ASY CABLE HV/FNT PNL SR80	1
	12634	CABLE REAR PNL/CONT OS SR80	1
	12633	CABLE RELAY COIL SR80	1
	12632	CABLE FNT PNL/CONT SR80	1
	12631	CABLE RIB 60/C SR80	1
	12630	CABLE RIB 10/C SR80	1
R7	12576	RES 0 0.01 1% 50M CHAS HT8	1
R6, 9	12348	RES 0 0.25 25W CHAS HT8	2
	12299	ASY PCB HV PHR SUP SR80 UNIT 2	4
X6, 14	12186	RELAY 1PST 15A8250V 24VDC	2
X3	12171	RELAY 2PST 5A8250V NO/NC 240CV	1
X8, 10	12170	RELAY 2PST 20A8250V 240CV	2
X4, 9, 11-13	12168	RELAY 3PST 5A8250V 240CV	7
15, 16			
T5	12103	TRANSF 115/230: 30V8-7A CT	1
C1	12101	CAP MFD 1000 450V ALUM CAN	1
R2	12089	RES K 6.0 5% 25W HW FIXED	1
T3	12086	TRANSF OUTPUT SR80	1
T4	12085	TRANSF OUTPUT SR80	1
S2	12055	SM 2POT 20A ON-ON TCL	1
S3	12054	SM 2POT 1A ON-OFF TCL MOM	1
X7, 19	12044	RELAY 1PST 15A 120VAC 24VDC	2
X2, 5, 17, 19	12043	RELAY 1PST 15A NO 24VDC	4
T2	12041	KNOB 1.25 MIL GRV	1
T1	12040	KNOB 1.25 MIL GRV .25 HOLE	1
	12039	KNOB 0.7 MIL GRV .25 HOLE PHTR	3
F1-6	12036	FUSE HOLDER HT8-481 BODY BUSS	8
F6, 7	11948	FUSE 7A 250V HOL	2
FAN	11334	FAN 120CFM 230V 50/60 HZ	1

REF. DES.	PART NO.	DESCRIPTION	QTY.
	12297	ASY PCB LOGIC	1
	12295	ASY PCB MEASUREMENT	1
F4, 5	983	FUSE 2.0A 250V HOA	2
F1	982	FUSE 0.5A 250V HOL	1
S1	98	SM 2POT TOGGLE 15A	1
F3, 8	952	FUSE 5A 250V HOA	2
F2	950	FUSE 1.5A 250V HOA	1
T2	9484	TRANSF VAR 250V 2.5A SUP	1
X1	9308	RELAY ARDMAT SP2 24VDC EP	1
MOV1-4	8868	VARIATOR 320V	4
FL1	8009	FILTER RFI 115-230V3 AMP OCR	1
D2	5232	DIODE BRIDGE 10A 500V CHAS MT	1
O1	4708	DIODE BRIDGE 25A 200V CHAS MT	1
	3294	TRANSF VAR 240V 0.5A SUP	1
R3	2183	RES 0 100 5% 12W	1

